

United States Army
Fort Monmouth, New Jersey

**Underground Storage Tank
Closure and Site Investigation
Report**

***Building 746
Main Post-West Area***

NJDEP UST Registration No. 0081533-120

April 2000

**UNDERGROUND STORAGE TANK
CLOSURE AND SITE INVESTIGATION REPORT**

BUILDING 746

**MAIN POST-WEST AREA
NJDEP UST REGISTRATION NO. 0081533-120**

APRIL 2000

PREPARED FOR:

**UNITED STATES ARMY, FORT MONMOUTH, NEW JERSEY
DIRECTORATE OF PUBLIC WORKS
BUILDING 167
FORT MONMOUTH, NJ 07703**

PREPARED BY:

**VERSAR
1900 FROST ROAD
SUITE 110
BRISTOL, PA 19007**

PROJECT NO. 4435-043

TABLE OF CONTENTS

EXECUTIVE SUMMARY	iv
1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES	1
1.1 OVERVIEW	1
1.2 SITE DESCRIPTION	2
1.2.1 Geological/Hydrogeological Setting	2
1.3 HEALTH AND SAFETY	4
1.4 REMOVAL OF UNDERGROUND STORAGE TANK	4
1.4.1 General Procedures	4
1.4.2 Underground Storage Tank Excavation and Cleaning	4
1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL	5
1.6 MANAGEMENT OF EXCAVATED SOILS	5
2.0 SITE INVESTIGATION ACTIVITIES	6
2.1 OVERVIEW	6
2.2 FIELD SCREENING/MONITORING	6
2.3 SOIL SAMPLING	7
3.0 CONCLUSIONS AND RECOMMENDATIONS	8
3.1 SOIL SAMPLING RESULTS	8
3.2 CONCLUSIONS AND RECOMMENDATIONS	8

TABLE OF CONTENTS (CONTINUED)

TABLES

- Table 1** **Summary of Post-Excavation Sampling Activities**
Table 2 **Post-Excavation Soil Sampling Results**

FIGURES

- Figure 1** **Site Location Map**
Figure 2 **Site Map**
Figure 3 **Cross Sectional View**
Figure 4 **Soil Sampling Location Map**

APPENDICES

- Appendix A** **NJDEP Standard Reporting Form**
Appendix B **Site Assessment Summary**
Appendix C **Waste Manifest**
Appendix D **UST Disposal Certificate**
Appendix E **Soil Analytical Data Package**
Appendix F **Photographs**
Appendix G **Electronic Data Deliverables**

EXECUTIVE SUMMARY

UST Closure

On October 2, 1997, a fiberglass underground storage tank (UST) was closed by removal in accordance with the New Jersey Department of Environmental Protection (NJDEP) underground storage tank procedures at the Main Post-West area of the U.S. Army Fort Monmouth, Fort Monmouth, New Jersey. The UST, NJDEP Registration No. 0081533-120 (Fort Monmouth ID No. 746), was located southwest of Building 746. UST No. 0081533-120 was a 550-gallon No. 2 fuel oil UST.

Site Assessment

The site assessment was performed by U.S. Army personnel in accordance with the NJDEP *Technical Requirements for Site Remediation* (N.J.A.C. 7:26E) and the NJDEP *Field Sampling Procedures Manual*. The sampling and laboratory analysis conducted during the site assessment were performed in accordance with Section 7:26E-2.1 of the *Technical Requirements for Site Remediation*. Soils surrounding the tank were screened visually and with air monitoring equipment for evidence of contamination. Following removal, the UST was inspected for corrosion holes or punctures. No holes or punctures were noted in the UST. Perched water was encountered at 5.0 feet below ground surface and no sheen was observed. Samples contained non-detectable levels of TPHC.

Site Restoration

Following receipt of all post-excavation soil sampling results, the excavation was backfilled with crushed stone, sand, and native backfill to grade and restored to its original condition.

Conclusions and Recommendations

Based on the post-excavation soil sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

No further action is proposed in regard to the closure and site assessment of UST No. 0081533-120 at Building 746.

1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES

1.1 OVERVIEW

One underground storage tank (UST), New Jersey Department of Environmental Protection (NJDEP) Registration No. 0081533-120, was closed at Building 746 at the Main Post-West area of U.S. Army Fort Monmouth, Fort Monmouth, New Jersey on October 2, 1997. Refer to site location map on Figure 1. This report presents the results of the Department of Public Works (DPW) implementation of the UST Decommissioning/Closure Plan approved by the NJDEP. The UST was a fiberglass 550-gallon tank containing No. 2 fuel oil.

Decommissioning activities for UST No. 0081533-120 complied with all applicable Federal, State and Local laws and ordinances in effect at the date of decommissioning. These laws included but were not limited to N.J.A.C. 7:14B-1 et seq., N.J.A.C. 5:23-1 et seq., and Occupational Safety and Health Administration (OSHA) 1910.146 & 1910.120. All permits including but not limited to the NJDEP-approved Decommissioning/Closure Plan were posted onsite for inspection. The decommissioning activities were conducted by DPW personnel who are registered and certified by the NJDEP for performing UST closure activities. Closure of UST No. 0081533-120 proceeded under the approval of the NJDEP Bureau of Federal Case Management (NJDEP-BFCM). The Standard Reporting Form and signed Site Assessment Summary form for UST No. 0081533-120 are included in Appendices A and B, respectively.

Based on inspecting the UST, field screening of subsurface soils and groundwater, and reviewing analytical results of collected soil samples, the DPW has concluded that no significant historical discharges are associated with the UST or associated piping.

This UST Closure and Site Investigation Report has been prepared by SMC Environmental Services Group, to assist the United States Army Directorate of Public Works (DPW) in complying with the NJDEP regulations. The applicable NJDEP regulations at the date of closure were the *Interim Closure Requirements for Underground Storage Tank Systems* (N.J.A.C. 7:14B-1 et seq. October 1990 and revisions dated November 1, 1991).

This report was prepared using information collected at the time of closure. Section 1 of this UST Closure and Site Investigation Report provides a summary of the UST decommissioning activities. Section 2 of this report describes the site investigation activities. Conclusions and recommendations, including the results of the soil sampling investigation, are presented in the final section of this report.

1.2 SITE DESCRIPTION

Building 746 is located in the Main Post-West area of the Fort Monmouth Army Base. UST No. 0081533-120 was located southwest of Building 746 and appurtenant copper piping ran approximately two (2) feet northwest from the UST to Building 746. A site map is provided on Figure 2.

1.2.1 Geological/Hydrogeological Setting

The following is a description of the geological/hydrogeological setting of the area surrounding Building 746. Included is a description of the regional geology of the area surrounding Fort Monmouth as well as descriptions of the local geology and hydrogeology of the Main Post area.

Regional Geology

Monmouth County lies within the New Jersey Section of the Atlantic Coastal Plain physiographic province. The Main Post, Charles Wood, and the Evans areas are located in what may be referred to as the Outer Coastal Plain subprovince, or the Outer Lowlands.

In general, New Jersey Coastal Plain formations consist of a seaward-dipping wedge of unconsolidated deposits of clay, silt, and gravel. These formations typically strike northeast-southwest with a dip ranging from 10 to 60 feet per mile and were deposited on Precambrian and lower Paleozoic rocks (Zapeczka, 1989). These sediments, predominantly derived from deltaic, shallow marine, and continental shelf environments, date from Cretaceous through the Quaternary Periods. The mineralogy ranges from quartz to glauconite.

The formations record several major transgressive/regressive cycles and contain units which are generally thicker to the southeast and reflect a deeper water environment. Over 20 regional geologic units are present within the sediments of the Coastal Plain. Regressive, upward coarsening deposits are usually aquifers (e.g., Englishtown and Kirkwood Formations, and the Cohansey Sand) while the transgressive deposits act as confining units (e.g., the Merchantville, Marshalltown, and Navesink Formations). The individual thicknesses for these units vary greatly (i.e., from several feet to several hundred feet). The Coastal Plain deposits thicken to the southeast from the Fall Line to greater than 6,500 feet in Cape May County (Brown and Zapeczka, 1990).

Local Geology

Based on the regional geologic map (Jablonski, 1968), the Cretaceous age Red Bank and Tinton Sands outcrop at the Main Post area. The Red Bank sand conformably overlies the Navesink Formation and dips to the southeast at 35 feet per mile. The upper member (Shrewsbury) of the Red Bank sand is a yellowish-gray to reddish brown clayey, medium-to-coarse-grained sand that contains abundant rock fragments, minor mica and glauconite (Jablonski). The lower member (Sandy Hook) is a dark gray to black, medium-to-fine grained sand with abundant clay, mica, and glauconite.

The Tinton sand conformably overlies the Red Bank Sand and ranges from a clayey medium to very coarse grained feldspathic quartz and glauconite sand to a glauconitic coarse sand. The color varies from dark yellowish orange or light brown to moderate brown and from light olive to grayish olive. Glauconite may constitute 60 to 80 percent of the sand fraction in the upper part of the unit (Minard, 1969). The upper part of the Tinton is often highly oxidized and iron oxide encrusted (Minard).

Hydrogeology

The water table aquifer in the Main Post area is identified as part of the "composite confining units", or minor aquifers. The minor aquifers include the Navesink formation, Red Bank Sand, Tinton Sand, Hornerstown Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation, and the basal clay of the Kirkwood Formation.

Based on records of wells drilled in the Main Post area, water is typically encountered at depths of 2 to 9 feet below ground surface (bgs). According to Jablonski, wells drilled in the Red Bank and Tinton Sands may produce 2 to 25 gallons per minute (gpm). Some well owners have reported acidic water that requires treatment to remove iron.

Due to the proximity of the Atlantic Ocean to Fort Monmouth, shallow groundwater may be tidally influenced and may flow toward creeks and brooks as the tide goes out, and away from creeks and brooks as the tide comes in. However, an abundance of clay lenses and sand deposits were noted in borings installed throughout Fort Monmouth. Therefore, the direction of shallow groundwater should be determined on a case-by-case basis.

Shallow groundwater is locally influenced within the Main Post area by the following factors:

- tidal influence (based on proximity to the Atlantic Ocean, rivers, and tributaries)
- topography
- nature of the fill material within the Main Post area
- presence of clay and silt lenses in the natural overburden deposits
- local groundwater recharge areas (i.e., streams, lakes)

Due to the fluvial nature of the overburden deposits (i.e., sand and clay lenses), shallow groundwater flow direction is best determined on a case-by-case basis. This is consistent with lithologies observed in borings installed within the Main Post area, which primarily consisted of fine-to-medium grained sands, with occasional lenses or laminations of gravel silt and/or clay.

Building 746 is located approximately 400 feet north of Husky Brook, the nearest water body. Based on the Main Post topography, the groundwater flow in the area of Building 746 is anticipated to be to the south.

1.3 HEALTH AND SAFETY

Before, during, and after all decommissioning activities, hazards at the work site which may have posed a threat to the Health and Safety of all personnel who were involved with, or were affected by, the decommissioning of the UST system were minimized. All areas, which posed, or may have been suspected to pose a vapor hazard were monitored by a qualified individual utilizing an organic vapor analyzer (OVA). The individual ascertained if the area was properly vented to render the area safe, as defined by OSHA.

1.4 REMOVAL OF UNDERGROUND STORAGE TANK

1.4.1 General Procedures

- All underground obstructions (utilities, etc.) were identified by the contractor performing the closure prior to excavation activities.
- All activities were carried out with the greatest regard to safety and health and the safeguarding of the environment.
- All excavated soils were visually examined and screened with an OVA for evidence of contamination. Potentially contaminated soils were identified and logged during closure activities.
- Surface materials (i.e., asphalt, concrete, etc.) were excavated and staged separately from all soil and recycled in accordance with all applicable regulations and laws.
- A Sub-Surface Evaluator from the DPW was present during all site assessment activities.

1.4.2 Underground Storage Tank Excavation and Cleaning

Prior to UST decommissioning activities, surficial soil was removed to expose the UST and associated piping. All free product present in the piping was drained into the UST, and the UST was purged to remove vapors prior to cutting and removal of the piping. After removal of the associated piping, a manway was made in the UST to allow for proper cleaning. The UST was completely emptied of all liquids prior to removal from the ground. Approximately 175 gallons of liquid from the UST and its associated piping were transported by Lionetti Oil Recovery Co. Inc to the Lionetti Oil Recovery Co. Inc. facility, a NJDEP-approved petroleum recycling and disposal company located in Old Bridge, New Jersey. Refer to Appendix C for the waste manifest.

The UST was cleaned prior to removal from the excavation in accordance with the NJDEP regulations. After the UST was removed from the excavation, it was staged on polyethylene sheeting and examined for holes. No holes or punctures were observed during the inspection by the Sub-Surface Evaluator. Soils surrounding the UST were screened visually and with an OVA for evidence of contamination. No evidence of contamination was observed. Soil screening was also performed along the piping run associated with the UST closure. Perched water was encountered at 5.0 feet below ground surface and no sheen was observed. See Figure 3 for a cross-sectional view of the excavated area.

1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL

The tank was transported to Mazza and Sons, Inc., Metal Recyclers. See Appendix D for a copy of the UST disposal certificate and Appendix F for photographs of the UST. The transportation of the UST was in compliance with all applicable regulations and laws.

The UST was labeled prior to transport with the following information:

- Site of origin
- Contact person
- NJDEP UST Facility ID number
- Former contents

1.6 MANAGEMENT OF EXCAVATED SOILS

Based on OVA air monitoring and TPHC analysis results from the post-excavation soil samples, no soils exhibited signs of contamination. Therefore, the excavated soils were used as backfill following removal of the UST.

2.0 SITE INVESTIGATION ACTIVITIES

2.1 OVERVIEW

The Site Investigation was managed and carried out by U.S. Army DPW personnel. All analyses were performed and reported by U.S. Army Fort Monmouth Environmental Laboratory, a NJDEP-certified testing laboratory. All sampling was performed under the direct supervision of a NJDEP Certified Sub-Surface Evaluator according to the methods described in the NJDEP *Field Sampling Procedures Manual* (1992). Sampling frequency and parameters analyzed complied with the NJDEP document *Interim Closure Requirements for Underground Storage Tank Systems* (October 1990 and revisions dated November 1, 1991) which was the applicable regulation at the date of the closure. All records of the Site Investigation activities are maintained by the Fort Monmouth DPW Environmental Office.

The following Parties participated in Closure and Site Investigation Activities:

- Subsurface Evaluator: Charles Appleby
Employer: U.S. Army, Fort Monmouth
Phone Number: (730) 532-6224
NJDEP Certification No.: 2056
- Analytical Laboratory: U.S. Army Fort Monmouth Environmental Laboratory
Contact Person: Daniel K. Wright
Phone Number: (908) 532-4359
NJDEP Company Certification No.: 13461
- Hazardous Waste Hauler: Lionetti Oil Recovery Co. Inc
Contact Person: Dan MacKay
Phone Number: (908) 721-0900
NJDEP Hazardous Waste Hauler No.: S6247

2.2 FIELD SCREENING/MONITORING

Field screening was performed by a NJDEP Certified Sub-Surface Evaluator using an OVA and visual observations to identify potentially contaminated material. Soil excavated from around the tank and appurtenant piping, as well as the UST excavation sidewalls and bottom, did not exhibit any evidence of potential contamination. Perched water was encountered at 5.0 feet below ground surface and no sheen was observed.

2.3 SOIL SAMPLING

On October 2, 1997, following the removal of the UST, post-excavation soil sample C was collected at the sidewall at a depth of 5.0 feet bgs. Due to utilities and site conditions, additional samples had to be collected on April 22, 2000, using a geoprobe. Post-excavation soil samples 1, 2, 3, 4, 5, and DUP 1 were collected from a total of five (5) locations of the UST excavation. Samples 1, 2, 3, 4, and DUP 1 were collected along the sidewall at a depth of 6.0 feet bgs. Excavation floor sample 5 was collected at a depth of 7.0 feet bgs. All samples were analyzed for total petroleum hydrocarbons (TPHC) and total solids.

U.S. Army personnel in accordance with the NJDEP Technical Requirements and the NJDEP Field Sampling Procedures Manual performed the site assessment. A summary of sampling activities including parameters analyzed is provided in Table 1. The post-excavation soil samples were collected using NJDEP *Field Sampling Procedures Manual* (1992) standard sampling procedures. Following soil sampling activities, the samples were chilled and delivered to U.S. Army Fort Monmouth Environmental Laboratory located in Fort Monmouth, New Jersey, for analysis.

3.0 CONCLUSIONS AND RECOMMENDATIONS

3.1 SOIL SAMPLING RESULTS

To evaluate soil conditions following removal of the UST, post-excavation soil samples were collected on October 2, 1997, and April 22, 2000, from a total of six (6) locations. All samples were analyzed for TPHC and total solids. The post-excavation sampling results were compared to the NJDEP residential direct contact total organic contaminants soil cleanup criteria of 10,000 mg/kg (N.J.A.C. 7:26D and revisions dated February 3, 1994). A summary of the analytical results and comparison to the NJDEP soil cleanup criteria is provided in Table 2 and the soil sampling locations are shown on Figure 4. The analytical data package is provided in Appendix E.

All post-excavation soil samples collected on October 2, 1997, and April 22, 2000, from the UST excavation and from below piping associated with the UST contained concentrations of TPHC below the NJDEP soil cleanup criteria. Samples contained non-detectable levels of TPHC.

3.2 CONCLUSIONS AND RECOMMENDATIONS

The analytical results for all post-excavation soil samples collected from the UST closure excavation at Building 746 were below the NJDEP soil cleanup criteria for total organic contaminants.

Based on the post-excavation sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

No further action is proposed in regard to the closure and site assessment of UST No. 0081533-120 at Building 746.

TABLES

TABLE 1

SUMMARY OF POST-EXCAVATION SAMPLING ACTIVITIES
BUILDING 746, MAIN POST-WEST AREA
FORT MONMOUTH, NEW JERSEY

Page 1 of 2

Sample ID	Date of Collection	Date Analysis Started	Matrix	Sample Type	Analytical Parameters*	Analysis Method
A	10/2/97	10/3/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
B	10/2/97	10/3/97	Soil	Post-Excavation	TPHC	OQA-QAM-025
C	10/2/97	10/3/97	Soil	Post-Excavation	TPHC	OQA-QAM-025

Note:

* TPHC Total Petroleum Hydrocarbons

TABLE 1

SUMMARY OF POST-EXCAVATION SAMPLING ACTIVITIES
BUILDING 746, MAIN POST-WEST AREA
FORT MONMOUTH, NEW JERSEY

Page 2 of 2

Sample ID	Date of Collection	Date Analysis Started	Matrix	Sample Type	Analytical Parameters*	Analysis Method
1	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025
2	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025
3	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025
4	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025
5	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025
DUP 1	4/22/00	4/25/00	Soil	Post-Excavation	TPHC	OQA-QAM-025

Note:

* TPHC Total Petroleum Hydrocarbons

TABLE 2

POST-EXCAVATION SOIL SAMPLING RESULTS
 BUILDING 746, MAIN POST-WEST AREA
 FORT MONMOUTH, NEW JERSEY

Page 1 of 2

Sample ID/ Depth	Sample Laboratory ID	Sample Date	Analysis Date	Analytical Method Used	Method Detection Limit (mg/kg)	Compound of Concern	Result (mg/kg) *	NJDEP Soil Cleanup Criteria ** (mg/kg)	Exceeds Cleanup Criteria
A/EXC. SOIL	3027.01	10/2/97	10/3/97	Total Solid	--	--	75.79	--	--
				TPHC	207	yes	ND	10,000	No
B/EXC. SOIL	3027.02	10/2/97	10/3/97	Total Solid	--	--	71.53	--	--
				TPHC	206	yes	ND	10,000	No
C/5.0=	3027.03	10/2/97	10/3/97	Total Solid	--	--	73.46	--	--
				TPHC	203	yes	ND	10,000	No

Note:

- * Total Solid results are expressed as a percentage.
- ** NJDEP Residential Direct Contact soil cleanup criteria for total organics
- Not detected above stated sample quantitation limit
- TPHC Total Petroleum Hydrocarbons

TABLE 2

POST-EXCAVATION SOIL SAMPLING RESULTS
 BUILDING 746, MAIN POST-WEST AREA
 FORT MONMOUTH, NEW JERSEY

Page 2 of 2

Sample ID/ Depth	Sample Laboratory ID	Sample Date	Analysis Date	Analytical Method Used	Method Detection Limit (mg/kg)	Compound of Concern	Result (mg/kg) *	NJDEP Soil Cleanup Criteria ** (mg/kg)	Exceeds Cleanup Criteria
1/6.0=	5373.01	422/00	4/25/00	Total Solid	--	--	83.26	--	--
				TPHC	187	yes	ND	10,000	No
2/6.0=	5373.02	422/00	4/25/00	Total Solid	--	--	82.57	--	--
				TPHC	189	yes	ND	10,000	No
3/6.0=	5373.03	422/00	4/25/00	Total Solid	--	--	80.35	--	--
				TPHC	194	yes	ND	10,000	No
4/6.0=	5373.04	422/00	4/25/00	Total Solid	--	--	81.34	--	--
				TPHC	190	yes	ND	10,000	No
5/7.0=	5373.05	422/00	4/25/00	Total Solid	--	--	81.05	--	--
				TPHC	191	yes	ND	10,000	No
DUP1/6.0=	5373.06	422/00	4/25/00	Total Solid	--	--	80.35	--	--
				TPHC	194	yes	ND	10,000	No

Note:

* Total Solid results are expressed as a percentage.

** NJDEP Residential Direct Contact soil cleanup criteria for total organics

-- Not detected above stated sample quantitation limit

TPHC Total Petroleum Hydrocarbons

FIGURES




FIGURE 1

LOCATION MAP
 Building 746
 Main-Post West
 Fort Monmouth Army Base
 Monmouth County, NJ

VERSAR
 Engineers, Managers, Scientists, & Planners
 Bristol, PA

Scale: 1" = 2000'

Date: Oct 1997


LONG BRANCH, N. J.

40073-C8-TF-024


1954

PHOTOREVISED 1981

DMA 6164 I SE -SERIES V822



NEW JERSEY
 QUADRANGLE LOCATION



SITE



FIGURE 2
SITE MAP
BUILDING 746
FORT MONMOUTH ARMY BASE
MONMOUTH COUNTY, NJ

VERSAR
ENGINEERS, MANAGERS, SCIENTISTS & PLANNERS
BRISTOL, PA.

SCALE: 1"=100'

DATE: OCT 1997





FIGURE 3
CROSS SECTIONAL VIEW
BUILDING 746
FORT MONMOUTH ARMY BASE
MONMOUTH COUNTY, NJ

VERSAR
 Engineers, Managers, Scientists & Planners
 Bristol, Pennsylvania

SCALE: NTS

DATE: Oct. 1997

BUILDING 746



LEGEND

- SOIL SAMPLE LOCATION (OCTOBER 2, 1997)
- SOIL SAMPLE LOCATION (APRIL 22, 2000)
- ▨ LIMIT OF EXCAVATION (OCTOBER 2, 1997)

NOTES:

1. ALL RESULTS IN MG/KG.
2. SEE TABLE 2 FOR NJDEP SOIL CLEANUP CRITERIA
3. BGS = BELOW GROUND SURFACE

FIGURE 4
SOIL SAMPLING LOCATION MAP
BUILDING 746
FORT MONMOUTH ARMY BASE
MONMOUTH COUNTY, NJ

VERSAR
ENGINEERS, MANAGERS, SCIENTISTS & PLANNERS
BRISTOL, PA.

SCALE: 1"=10'

DATE: OCT 1997

APPENDIX A
NJDEP-STANDARD REPORTING FORM



State of New Jersey
 Department of Environmental Protection and Energy
 Division of Responsible Party Site Remediation
 CN 028
 Trenton, NJ 08625-0029

ATTN: UST Program
 (609) 984-3156

For State Use Only

Date Rec'd. _____
 Auth. _____
 Routing _____
 UST NO. _____

STANDARD REPORTING FORM
 for reporting activities at an UST facility:

- | | |
|--|---|
| <input checked="" type="checkbox"/> General Facility Information Changes | <input type="checkbox"/> Sale or Transfer |
| <input checked="" type="checkbox"/> Closure (Abandonment or Removal) | <input type="checkbox"/> Substantial Modification |
| <input type="checkbox"/> Temporary Closure | <input type="checkbox"/> Financial Responsibility |
| <input type="checkbox"/> Change in Service | <input type="checkbox"/> Address Change Only |

Check ONLY One Type of Activity - Complete Form For That Activity

(More than one tank can be listed per activity)

*** NOTE *** ALL NEW tank installations at existing registered facilities must submit a Registration Questionnaire for the new tanks.

Answer questions 1 through 5 and others as applicable.

1. Company name and address (as it appears on registration questionnaire):

U.S. Army Fort Monmouth
DPW - Bldg 173
ATTN: Charles Appleby

2. Facility name and location (# different from above):

MAIN POST WEST

3. Contact person for this activity:

Charles Appleby
 Telephone Number: (732) 532-6254

4. The identification number of the affected tank as it appears in Question Number 12 on the Registration Questionnaire:

Bldg. 746
0081533

5. Registration Number (if known):

UST - 120

6. For GENERAL FACILITY INFORMATION changes (address, telephone, contact person, etc. - supply NEW information only):

- a. Facility name: _____
 b. Facility location: _____
 c. Owner's mailing address: _____
 _____ NJ _____
 d. Block: _____ Lot: _____
 e. Contact person (facility operator): _____
 f. Contact telephone number: (____) _____
 g. Other (Specify): _____

(OVER)

2-71

UST
 1/1/16
 150

7. For CLOSURE (abandonment or removal - check all that apply):

a. Abandonment Date: ___/___/___ Case No: _____

Attach the necessary implementation schedule (3 copies) and all documentation needed for abandonment per N.J.A.C. 7:14B-9.1 (d).

b. Removal Date: 10/2/97 Case No. NA

Attach the necessary implementation schedule (3 copies).

8. For CHANGES IN HAZARDOUS SUBSTANCES STORED (check all that apply):

a. Temporary Closure (12 month maximum time - see N.J.A.C. 7:14B-9.1(b)). Remove all hazardous substances; leave tank in place.

b. Change in service from a regulated substance to a non-regulated substance. Tank must be cleaned and site assessment performed per N.J.A.C. 7:14B-9.1(e).

c. Changes in service from one regulated hazardous substance to another regulated hazardous substance.

Tank No. _____ Old _____ New _____

Tank No. _____ Old _____ New _____

Tank No. _____ Old _____ New _____

(Attach additional sheets if more space is needed)

9. For TRANSFER OF OWNERSHIP: Effective Date: ___/___/___

a. New Owner (operator) _____

b. New Facility Name _____

NJ _____

County

c. Closing Attorney _____ Tele: (____) _____ - _____

10. For SUBSTANTIAL MODIFICATIONS (to include any retrofitted activity - e.g. the addition of spill/overfill protection, monitoring systems, cathodic protection, etc.):

a. Type of Modification _____ Date: ___/___/___

b. * NOTE * Substantial modifications require a permit under N.J.A.C. 7:14B-10.

11. For changes in FINANCIAL RESPONSIBILITY to (check appropriate changes and attach copies of new information):

a. Policy Type:

d. Company/Carrier:

b. Policy Number:

e. Expiration Date:

c. Other:

(Specify)

NOTE: ALL appropriate and applicable permits, licenses and certificates required by the above activity(ies) from any local, state and/or federal agencies must be obtained separately from this notification.

CERTIFICATION

This registration form shall be signed by the highest ranking individual at the facility with overall responsibility for that facility (N.J.A.C. 7:14B-2.3 (a) 1).

"I certify under penalty of law that the information provided in this document is true, accurate and complete. I am aware that there are significant civil and criminal penalties for submitting false, inaccurate or incomplete information, including fines and/or imprisonment."

Signature: [Signature]

Name (print or type): MR. James Ott

Title: Director of Public Works Date: 10/3/97

APPENDIX B
SITE ASSESSMENT SUMMARY

Site Remediation Program

UST Site/Remedial Investigation Report Certification Form

A. Facility Name : U.S. Army Fort Monmouth New Jersey

Facility Street Address : Directorate of Public Works Building 173

Municipality: Oceanport County : Monmouth

Block: Lot(s): Telephone Number : 732-532-6224

B. Owner (RP)'s Name:

Street Address: City :

State: Zip: Telephone Number :

C. (Check as appropriate)

- Site Investigation Report (SIR) \$500 Fee
Remedial Investigation Report (RIR) \$1000 Fee

X NA - Federal Agreement

D. (Complete all that apply)

- Assigned Case Manager : Ian Curtis, Federal Case Manager
UST Registration Number : 81533-120 (7 digits)
Incident Report Number (10 or 12 digits)
Tank Closure Number : Federal Case Manager

E. Certification by the Subsurface Evaluator:

The attached report conforms to the specific reporting requirements of N.J.A.C. 7:26EYes No

Name: Charles Appleby Signature: See signed subsurface removal log UST Cert. No.: 2056

Firm: U.S. Army Fort Monmouth Firm's UST Cert. Number: NA-U.S. Army

Firm Address: Directorate of Public Works Building 173 City: Fort Monmouth

State: NJ Zip: 07703 Telephone Number : 732-532-6224

(NOTE: Certification numbers required only if work was conducted on USTs regulated per N.J.S.A. 58:10A-21 et seq.)

F. Certification by the Responsible Party(ies) of the Facility:

The following certification shall be signed [according to the requirements of N.J.A.C. 7:14B-1.7(b)]as follows:

- 1. For a Corporation by a person authorized by a resolution of the board of directors to sign the document.
2. For a partnership or sole proprietorship, by a general partner or the proprietor, respectively; or
3. For a municipality, State, federal or other public agency by either a principal executive officer or ranking elected Official.

"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attached documents, and that based on my inquiry of those individuals responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant civil penalties for knowingly submitting false, inaccurate, or incomplete information and that I am committing a crime of the fourth degree if I make a written false statement which I do not believe to be true. I am also aware that if I knowingly direct or authorize the violation of any statute, I am personally liable for the penalties."

Name (Print or Type): James Ott Title: Directorate of Public Works

Signature: [Handwritten Signature]

Company Name: U.S. Army Fort Monmouth

Date: 7/31/00


**US ARMY, SELFM-PW-EV
DAILY UST SUBSURFACE REMOVAL LOG**

BLDG.#: 746 REG.#: 81533 - 120 CLOSURE#: Fed Case Mgo.
 DATE: 10/2/97 TOA: 1330 TOD: 1700
 GOV. SSE: Charles Appleby NJDEP CERT.#: _____
 REMOVAL/CONTRACTOR: TVS Inc.
 CLOSURE SUPERVISOR: GARY Tranello NJDEP CERT.#: _____
 WEATHER: Sunny Cool ~70°F

ACTIVITY	YES / NO
THE SUPERVISOR (CLOSURE CERT.) WAS ON-SITE DURING ALL CLOSURE RELATED ACTIVITIES	YES
THE SSE WAS ON-SITE DURING UST REMOVAL AND SITE SCREENING AND SAMPLING ACTIVITIES	
ALL ON-SITE PERSONNEL HAD TRAINING IAW ALL SAFETY REQUIREMENTS (E.G. 29CFR)	YES
A CONFINED ENTRY PERMIT WAS COMPLETED AND POSTED ON-SITE BY THE CONTRACTOR <u>NA</u>	NA
THE UST WAS PLACED ONTO PLASTIC, SCRAPED OFF, INSPECTED FOR HOLES AND PHOTOGRAPHED	YES
A DISCHARGE WAS REPORTED TO THE NJDEP (609-292-7172), CASE# <u>NA</u>	NO
PHOTOS HAVE UST#, BLDG. #, DATE, TIME, NAME OF SSE AND DESCR. WRITTEN ON BACK	YES TUS
^{probed} GROUNDWATER WAS ENCOUNTERED AT <u>5</u> FEET BG, A SHEEN (WAS/WAS NOT) OBSERVED ON GW	
IF OVA/Hnu WAS USED: WAS IT CAL. AND FOUND TO BE OPERATIONAL (cal. data on COC)	YES NO
IF SAMPLES WERE TAKEN: COC, SCALED SITE MAP (VERT. SOIL HORIZONS AND PLOT PLAN)	TUS
ALL SAMPLE COLLECTION ACTIVITIES WERE AS DESCRIBED IN THE NJDEP FSPM, 1992	YES
ALL SAMPLING WAS BIASED TOWARD HIGHEST OVA/FID RECORDED SITES IAW 7:26E-3.6 et seq.	ALL NO
ALL PETROL. CONT. SOILS WERE SECURED FROM THE WEATHER BY CLOSE OF BUSINESS TODAY	NA
THE SSE AUTHORIZED BACKFILLING THE EXCAVATION (STONE TO 1" ABOVE GROUNDWATER)	YES
ADDITIONAL NOTES WERE TAKEN AND ARE RECORDED ON THE BACK OF THIS FORM	YES
THE FOLLOWING DOCUMENTS WERE ADDED TO THE PROJECT FOLDER TODAY: (CIRCLE EACH) SCRAP TICKET, ^{NA} CSE PERMIT, ACCIDENT REPORT, HAZ. WASTE MANIFEST, DAILY UST CLOSURE LOG, SCALED SITE MAP (SAMPLING), SRF-CLOSURE, CHAIN OF CUSTODY, SOIL ANALYTICAL RESULTS, CLEAN FILL TICKETS (IN YDS ³), PHOTOGRAPHS (UST, EXCAVATION, SAMPLING POINTS)	

CHECK ALL BOXES, LEAVE NO BLANK

I certify under penalty of law that tank decommissioning activities were performed in compliance with N.J.A.C. 7:14B-9.2(b)3 and 7:26 et seq.. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment.

SIGNATURE:  DATE: 10/2/97

ca\ms\ust\removal\sitessls.doc

* Contractor Did not feel it was Required.
 But Did it After Discussion.

APPENDIX C
WASTE MANIFEST



RD. 1, BOX 5A - OLD BRIDGE, NJ 08857

NON-HAZARDOUS WASTE MANIFEST

1. Generator's US EPA ID No.

NJ.3.21.00.2.0597

Manifest Document No.

08113

2. Page 1 of 1

NHZ 008113

3. Generator's Name and Mailing Address

U.S. ARMY COMMUNICATIONS ELECTRONICS COMMAND MAIN POST
C/O J. FALLON BLDG 173 ATTN: SELFM-PW-EV
FORT MONMOUTH, N.J. 07703

4. Generator's Phone (732) 532-6223

5. Transporter 1 Company Name

LIONETTI OIL RECOVERY CC INC

6. US EPA ID Number

N J D 0 8 4 0 4 4 0 6 4

A. Transporter's Phone

908 721-0900

7. Transporter 2 Company Name

8. US EPA ID Number

B. Transporter's Phone

9. Designated Facility Name and Site Address

LIONETTI OIL RECOVERY CO INC DBA LORCO PETROLEUM SVCS
RUNYON&CHEESEQUAKE RDS
OLD BRIDGE, NJ 08857

10. US EPA ID Number

N J D 0 8 4 0 4 4 0 6 4

C. Facility's Phone

908 721-0900

11. Waste Shipping Name and Description

a. PETROLEUM OIL (PETROLEUM OIL)
COMBUSTIBLE LIQUID UN1270 PGIII

12. Containers

No. Type

13. Total Quantity

14. Unit Wt/Vol

0 0 1 T 62450 G

GENERATOR

D. Additional Descriptions for Materials Listed Above

T, L PETROLEUM OIL 42%
WATER 58%

E. Handling Codes for Wastes Listed Above

T04 FILTRATION

15. Special Handling Instructions and Additional Information

24 HR EMERGENCY RESPONSE#(908) 721-0900
DECAL#8704 ERG#128 DEXSIL TEST KIT RESULTS PPM
MANIFEST USED FOR TRACKING PURPOSES ONLY

16. GENERATOR'S CERTIFICATION: I certify the materials described above on this manifest are not subject to federal regulations for reporting proper disposal of Hazardous Waste.

Printed/Typed Name

PINKER, M. DESAI

Signature

[Signature]

Month Day Year

11 10 97

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name

DAN MACKAY

Signature

[Signature]

Month Day Year

11 10 97

18. Transporter 2 Acknowledgement of Receipt of Materials

Printed/Typed Name

Signature

Month Day Year

19. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of waste materials covered by this manifest except as noted in Item 19.

Printed/Typed Name

[Signature]

Signature

[Signature]

Month Day Year

11 10 97

TRANSPORTER

FACILITY

ORIGINAL - RETURN TO GENERATOR

APPENDIX D
UST DISPOSAL CERTIFICATE

APPENDIX E
SOIL ANALYTICAL DATA PACKAGE

US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY
NJDEPE # 13461

REPORT OF ANALYSIS

Client: U.S. Army
DPW, SELFM-PW-EV
Bldg. 173
Ft. Monmouth, NJ 07703

Project: Total Petroleum Hydrocarbons
96-1262
Bldg. 746

Project # 3027
Date Rec. 10/03/97
Date Comp. 10/03/97
Released by:



Daniel K. Wright
Laboratory Director

Table of Contents

<u>Section</u>	<u>Pages</u>
Cover Sheet	1
Table of Contents	2
Method Summary	3
Conformance/Non-Conformance	4
Chain of Custody	5-6
Results Summary	7
Initial Calibration Summary	8
Continuing Calibration Summary	9-10
Surrogate Results Summary	11
MS/MSD Results Summary	12
Quality Control Spike Summary	13
Raw Sample Data	14-19
Laboratory Deliverable Checklist	20

Method Summary

NJDEP Method OQA-QAM-025-10/97

Gas Chromatographic Determination of Total Petroleum Hydrocarbons in Soil

Fifteen grams (15g)(wet weight) of a soil sample is added to a 125 mL acid cleaned, solvent rinsed, capped Erlenmeyer flask. 15g anhydrous sodium sulfate is added to dry sample. Surrogate standard spiking solution is then added to the flask.

Twenty five milliliters(25mL) Methylene Chloride is added to the flask and it is secured on a gyrotory shaker table. The agitation rate is set to 400rpm and the sample is shaken for 30 minutes. The flask is the removed from the table and the particulate matter is allowed to settle. The extract is transferred to a Teflon capped vial. A second 25mL of Methylene Chloride is added to the flask and shaken for an additional 30 minutes. The flask is again removed and allowed to settle. The extracts are combined in the vial then transferred to a 1mL autosampler vial.

The extract is then injected directly into a GC-FID for analysis. The sample is analyzed for petroleum hydrocarbons covering a range of C8-C42 including pristane and phytane. Total Petroleum Hydrocarbon concentration is determined by integrating between 5 minutes and 22 minutes. The baseline is established by starting the integration after the end of the solvent peak and stopping after the last peak.

The final concentration of Total Petroleum Hydrocarbons is calculated using percent solid, sample weight and concentration.

PHC Conformance/Non-conformance Summary Report


	<u>No</u>	<u>Yes</u>
1. Method Detection Limits provided.	—	✓
2. Method Blank Contamination - If yes, list the sample and the corresponding concentrations in each blank. _____ _____	✓	—
3. Matrix Spike Results Summary Meet Criteria. (If not met, list the sample and corresponding recovery which falls outside the acceptable range). _____ _____	—	✓
4. Duplicate Results Summary Meet Criteria. _____ (If not met, list the sample and corresponding recovery which falls outside the acceptable range). _____ _____	—	✓
5. IR Spectra submitted for standards, blanks, & samples	—	NA
6. Chromatograms submitted for standards, blanks, and samples if GC fingerprinting was conducted.	—	✓
7. Analysis holding time met. (If not met, list number of days exceeded for each sample) _____ _____	—	✓
Additional Comments: _____ _____ _____		

Laboratory Authentication Statement

I certify under penalty of law, where applicable, that this laboratory meets the Laboratory Performance Standards and Quality Control requirements specified in N.J.A.C. 7:18 and 40 CFR Part 136 for Water and Wastewater Analyses and SW 846 for Solid Waste Analysis. I have personally examined the information contained in this report, and to the best of my knowledge, I believe that the submitted information is true, accurate, complete, and meets the above referenced standards where applicable. I am aware that there are significant penalties for purposefully submitting falsified information, including the possibility of a fine and imprisonment.



Daniel K. Wright
Laboratory Manager



Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

Chain of Custody Record

Customer: DPW-ENV		Project No: 96-1262		Analysis Parameters						Comments:			
Phone #:		Location: B. 746								* = SAMPLES KEPT BELOW 4°C.			
() DERA (X) OMA () Other:		Samplers Name / Company: GARY DiMARTINIS - TUS		Sample #							Remarks / Preservation Method		
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles	TPAC	OTO SALINOS	MUNSELL				OUA	
3027.01	746-A	10-2-97	1527	SOIL	1	X	X	X				ND	EXCAVATED SOIL *
3027.02	-B	↓	1531	↓	↓	↓	↓	↓				ND	EXCAVATED SOIL ↓
3027.03	-C	↓	1452	↓	↓	↓	↓	↓				ND	SIDE WALL @ 5.0' ↓
NOTE: OUA (#A52114) CALIBRATED W/ 95 ppm CH4 & ZERO (0) AIR @ 1445 HRS ON 10/2/97 by G. DiMARTINIS.													
Relinquished by (signature): <i>[Signature]</i>		Date/Time: 10-3-97 0920		Received by (signature): <i>[Signature]</i>		Relinquished by (signature):		Date/Time:		Received by (signature):			
Relinquished by (signature):		Date/Time:		Received by (signature):		Relinquished by (signature):		Date/Time:		Received by (signature):			
Report Type: () Full, (X) Reduced, () Standard, () Screen / non-certified						Remarks: DEDICATED SAMPLING TOOLS USED.							
Turnaround time: (X) Standard 4 wks, () Rush Days, () ASAP Verbal Hrs.													

Report of Analysis
 U.S. Army, Fort Monmouth Environmental Laboratory
 NJDEP Certification # 13461

Client : U.S. Army **Lab. ID # :** 3027
 DPW. SELFM-PW-EV **Date Rec'd:** 03-Oct-97
 Bldg. 173 **Analysis Start:** 03-Oct-97
 Ft. Monmouth, NJ 07703 **Analysis Complete:** 04-Oct-97

Analysis: OQA-QAM-025 **UST Reg. #:**
Matrix: Soil **Closure #:**
Analyst: D.DEINHARDT **DICAR #:**
Ext. Meth: Shake **Location #:** B.746

Sample	Field ID	Dilution Factor	Weight (g)	% Solid	MDL (mg/kg)	TPHC Result (mg/kg)
3027.01	746-A	1.00	14.99	75.79	207	ND
3027.02	746-B	1.00	15.93	71.53	206	ND
3027.03	746-C	1.00	15.78	73.46	203	ND
METHOD BLANK	3-Oct-97	1.00	15.00	100.00	157	ND

ND = Not Detected
 MDL = Method Detection Limit


 Daniel K. Wright
 Laboratory Director


LABORATORY DELIVERABLES CHECKLIST AND NON-CONFORMANCE SUMMARY

THIS FORM MUST BE COMPLETED BY THE LABORATORY OR ENVIRONMENTAL CONSULTANT AND ACCOMPANY ALL DATA SUBMISSIONS

The following Laboratory Deliverables checklist and Non-Conformance Summary shall be included in the data submission. All deviations from the accepted methodology and procedures, of performance values outside acceptable ranges shall be summarized in the Non-Conformance Summary. The Technical Requirements for Site Remediation, effective June 7, 1993, provides further details. The document shall be bound and paginated, contain a table of contents, and all pages shall be legible. Incomplete packages will be returned or held without review until the data package is completed.

It is recommended that the analytical results summary sheets listing all targeted and non-targeted compounds with the method detection limits, practical quantitation limits, and the laboratory and/or sample numbers be included in one section of the data package and in the main body of the report.

- 1. Cover page, Title Page listing Lab Certification #, facility name and address, & date of report submitted
- 2. Table of Contents submitted
- 3. Summary Sheets listing analytical results for all targeted and non-targeted compounds submitted
- 4. Document paginated and legible
- 5. Chain of Custody submitted
- 6. Samples submitted to lab within 48 hours of sample collection
- 7. Methodology Summary submitted
- 8. Laboratory Chronicle and Holding Time Check submitted
- 9. Results submitted on a dry weight basis
- 10. Method Detection Limits submitted
- 11. Lab certified by NJDEP for parameters of appropriate category of parameters or a member of the USEPA CLP

Laboratory Manager or Environmental Consultant's Signature 
Date 2/2/20

Laboratory Certification #13461

*Refer to NJAC 7:26E - Appendix A, Section IV - Reduced Data Deliverables - Non-USEPA/CLP Methods for further guidance

FORT MONMOUTH ENVIRONMENTAL TESTING LABORATORY

DIRECTORATE OF PUBLIC WORKS

PHONE: (732) 532-6224 FAX: (732) 532-6263

WET-CHEM - METALS - ORGANICS - FIELD SAMPLING

CERTIFICATIONS: NJDEP #13461, NYSDOH #11699



ANALYTICAL DATA REPORT
Fort Monmouth Environmental Laboratory
ENVIRONMENTAL DIVISION
Fort Monmouth, New Jersey
PROJECT: UST Program

Bldg. 746

Field Sample Location	Laboratory Sample ID#	Matrix	Date and Time of Collection	Date Received
B-1 6'	5373.01	Soil	22-Apr-00 10:00	04/24/00
B-2 6'	5373.02	Soil	22-Apr-00 10:15	04/24/00
B-3 6'	5373.03	Soil	22-Apr-00 10:20	04/24/00
B-4 6'	5373.04	Soil	22-Apr-00 10:30	04/24/00
B-5 7'	5373.05	Soil	22-Apr-00 10:40	04/24/00
DUP. 6'	5373.06	Soil	22-Apr-00	04/24/00

ANALYSIS:
FORT MONMOUTH ENVIRONMENTAL LAB
TPHC, %SOLIDS

ENCLOSURE:
CHAIN OF CUSTODY
RESULTS


Daniel Wright/Date
Laboratory Director

LABORATORY DELIVERABLES CHECKLIST AND NON-CONFORMANCE SUMMARY

THIS FORM MUST BE COMPLETED BY THE LABORATORY OR ENVIRONMENTAL CONSULTANT AND ACCOMPANY ALL DATA SUBMISSIONS

The following Laboratory Deliverables checklist and Non-Conformance Summary shall be included in the data submission. All deviations from the accepted methodology and procedures, of performance values outside acceptable ranges shall be summarized in the Non-Conformance Summary. The Technical Requirements for Site Remediation, effective June 7, 1993, provides further details. The document shall be bound and paginated, contain a table of contents, and all pages shall be legible. Incomplete packages will be returned or held without review until the data package is completed.

It is recommended that the analytical results summary sheets listing all targeted and non-targeted compounds with the method detection limits, practical quantitation limits, and the laboratory and/or sample numbers be included in one section of the data package and in the main body of the report.

- | | |
|--|-------------------------------------|
| 1. Cover page, Title Page listing Lab Certification #, facility name and address, & date of report submitted | <input checked="" type="checkbox"/> |
| 2. Table of Contents submitted | <input checked="" type="checkbox"/> |
| 3. Summary Sheets listing analytical results for all targeted and non-targeted compounds submitted | <input checked="" type="checkbox"/> |
| 4. Document paginated and legible | <input checked="" type="checkbox"/> |
| 5. Chain of Custody submitted | <input checked="" type="checkbox"/> |
| 6. Samples submitted to lab within 48 hours of sample collection | <input checked="" type="checkbox"/> |
| 7. Methodology Summary submitted | <input checked="" type="checkbox"/> |
| 8. Laboratory Chronicle and Holding Time Check submitted | <input checked="" type="checkbox"/> |
| 9. Results submitted on a dry weight basis | <input checked="" type="checkbox"/> |
| 10. Method Detection Limits submitted | <input checked="" type="checkbox"/> |
| 11. Lab certified by NJDEP for parameters of appropriate category of parameters or a member of the USEPA CLP | <input checked="" type="checkbox"/> |

Laboratory Manager or Environmental Consultant's Signature

Date 4/28/02



Laboratory Certification #13461

*Refer to NJAC 7:26E - Appendix A, Section IV - Reduced Data Deliverables - Non-USEPA/CLP Methods for further guidance.

Laboratory Authentication Statement

I certify under penalty of law, where applicable, that this laboratory meets the Laboratory Performance Standards and Quality Control requirements specified in N.J.A.C. 7:18 and 40 CFR Part 136 for Water and Wastewater Analyses and SW-846 for Solid Waste Analysis. I have personally examined the information contained in this report and to the best of my knowledge, I believe that the submitted information is true, accurate, complete and meets the above referenced standards where applicable. I am aware that there are significant penalties for purposefully submitting falsified information, including the possibility of a fine and imprisonment.




Daniel K. Wright
Laboratory Manager

000030


APPENDIX F

ELECTRONIC DATA DELIVERABLES



Bldg. 746 UST Site Samples GPS Map

US State Plane 1983
 New Jersey (NY East) 2900
 NAD 1983 (Conus)



746 with jst c r050612b.cor
 7/10/2000
 Pathfinder Office



BLDG. 746 UST SAMPLES GPS POSITIONS & COORDINATES

US STATE PLANE 1983 NJ (NY EAST) 2900 NAD 1983 (CONUS)


(INJ US SURVEY FEET)

SAMPLE POINTS

<u>POSITION / DESC.</u>	<u>Y COORD. (NORTHING)</u>	<u>X COORD (EASTING)</u>
C	538025.864	618604.383


REFERENCE POINTS

<u>POSITION / DESC.</u>	<u>Y COORD. (NORTHING)</u>	<u>X COORD (EASTING)</u>
NATURAL GAS MARKER	538019.784	618619.499
TELE POLE	537997.39	618581.35



Bldg. 746 UST Follow-up Soils GPS Map

US State Plane 1983
 New Jersey (NY East) 2900
 NAD 1983 (Conus)



746 r050612b.cor
 5/12/2000
 Pathfinder Office
Trimble

BLDG. 746 UST FOLLOW-UP SOILS GPS POSITIONS & COORDINATES

US STATE PLANE 1983 NJ (NY EAST) 2900 NAD 1983 (CONUS)

(IN US SURVEY FEET)

SAMPLE POINTS

<u>POSITION / DESC.</u>	<u>Y COORD. (NORTHING)</u>	<u>X COORD. (EASTING)</u>
B-5	538022.19	618606.142
B-3	538020.436	618602.953
B-2	538025.379	618603.113
B-1	538023.785	618609.172
B-4	538019.699	618607.617

REFERENCE POINTS

<u>POSITION / DESC.</u>	<u>Y COORD. (NORTHING)</u>	<u>X COORD. (EASTING)</u>
NATURAL GAS MARKER	538019.784	618619.499
TELE POLE	537997.39	618581.35