

**United States Army**  
Fort Monmouth, New Jersey

**COPY**

---

# **Underground Storage Tank Closure and Site Investigation Report**

***Building 2537  
Charles Wood Area***

---

**NJDEP UST Registration No. 81515-27  
Dicar No. 97-5-27-1421-04**

**April 1998**

**UNDERGROUND STORAGE TANK  
CLOSURE AND SITE INVESTIGATION REPORT**

**BUILDING 2537**

**CHARLES WOOD AREA  
NJDEP UST REGISTRATION NO. 81515-27**

**APRIL 1998**

**PREPARED FOR:**

**UNITED STATES ARMY, FORT MONMOUTH, NEW JERSEY  
DIRECTORATE OF PUBLIC WORKS  
BUILDING 167  
FORT MONMOUTH, NJ 07703**

**PREPARED BY:**

**SMC ENVIRONMENTAL SERVICES GROUP  
501 ALLENDALE ROAD  
KING OF PRUSSIA, PA 19406**

**PROJECT NO. 2429-3080**

# TABLE OF CONTENTS

<b>EXECUTIVE SUMMARY</b>	<b>iv</b>
<b>1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING ACTIVITIES</b>	<b>1</b>
<b>1.1 OVERVIEW</b>	<b>1</b>
<b>1.2 SITE DESCRIPTION</b>	<b>2</b>
<b>1.2.1 Geological/Hydrogeological Setting</b>	<b>2</b>
<b>1.3 HEALTH AND SAFETY</b>	<b>4</b>
<b>1.4 REMOVAL OF UNDERGROUND STORAGE TANK</b>	<b>4</b>
<b>1.4.1 General Procedures</b>	<b>4</b>
<b>1.4.2 Underground Storage Tank Excavation and Cleaning</b>	<b>4</b>
<b>1.5 UNDERGROUND STORAGE TANK         TRANSPORTATION AND DISPOSAL</b>	<b>5</b>
<b>1.6 MANAGEMENT OF EXCAVATED SOILS</b>	<b>5</b>
<b>2.0 SITE INVESTIGATION ACTIVITIES</b>	<b>6</b>
<b>2.1 OVERVIEW</b>	<b>6</b>
<b>2.2 FIELD SCREENING/MONITORING</b>	<b>6</b>
<b>2.3 SAMPLING</b>	<b>6</b>
<b>3.0 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>8</b>
<b>3.1 SAMPLING RESULTS</b>	<b>8</b>
<b>3.2 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>8</b>

## TABLE OF CONTENTS (CONTINUED)

### TABLES

<b>Table 1</b>	<b>Summary of Post-Excavation Sampling Activities</b>
<b>Table 2</b>	<b>Post-Excavation Soil Sampling Results</b>
<b>Table 3</b>	<b>Post-Excavation Groundwater Sampling Results</b>

### FIGURES

<b>Figure 1</b>	<b>Site Location Map</b>
<b>Figure 2</b>	<b>Site Map</b>
<b>Figure 3</b>	<b>Cross Sectional View</b>
<b>Figure 4</b>	<b>Sampling Location Map</b>

### APPENDICES

<b>Appendix A</b>	<b>NJDEP Closure Approval Letter</b>
<b>Appendix B</b>	<b>Site Assessment Summary</b>
<b>Appendix C</b>	<b>Waste Manifest</b>
<b>Appendix D</b>	<b>UST Disposal Certificate</b>
<b>Appendix E</b>	<b>Soil Analytical Data Package</b>
<b>Appendix F</b>	<b>Groundwater Analytical Data Package</b>
<b>Appendix G</b>	<b>Photographs</b>

## EXECUTIVE SUMMARY

### UST Closure

On May 27, 1997, a steel underground storage tank (UST) was closed by removal in accordance with the New Jersey Department of Environmental Protection (NJDEP) closure approval letter dated July 18, 1995 at the Charles Wood area of the U.S. Army Fort Monmouth Base, Fort Monmouth, New Jersey. The UST, NJDEP Registration No. 81515-27 (Fort Monmouth ID No. 2537), was located south of Building 2537 (Pistol Range). UST No. 81515-27 was a 1,000 gallon No. 2 fuel oil Tank. The fill port was located directly above the tank.

### Site Assessment

The site assessment was performed by U.S. Army personnel in accordance with the NJDEP *Technical Requirements for Site Remediation* (N.J.A.C. 7:26E) and the NJDEP *Field Sampling Procedures Manual*. The sampling and laboratory analysis conducted during the site assessment were performed in accordance with N.J.A.C. 7:26E. Soils surrounding the tank were screened visually and with air monitoring equipment for evidence of contamination. Stained soil was encountered in the excavation area. The NJDEP hotline was called and the case was assigned Dicar No. 97-5-27-1421-04. A total of 15 cubic yards of contaminated soil were removed on May 28 and 29, 1997.

Perched water was encountered at 6.0 feet below ground surface (bgs) and no sheen was observed. Soil samples collected after the removal of the contaminated soil contained non-detectable levels of total petroleum hydrocarbons (TPHC). Post-excavation groundwater sampling results, obtained from perched water in the excavation, contained non-detectable levels of Benzene #2, Toluene #2, Ethyl benzene #2, p+ m-Xylene #2, and o-Xylene #2.

### Site Restoration

Following receipt of all post-excavation soil sampling results, the excavation was backfilled to grade with crushed stone and native topsoil and restored to its original condition.

### Conclusions and Recommendations

Based on the post-excavation soil sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

Based on the post-excavation groundwater sampling results, groundwater with Benzene #2, Toluene #2, Ethyl benzene #2, p+ m-Xylene #2, and o-Xylene #2 concentrations exceeding their respective NJDEP ground water quality standards, do not exist in the former location of the UST.

No further action is proposed in regard to the closure and site assessment of UST No. 81515-27 at Building 2537.

## **1.0 UNDERGROUND STORAGE TANK DECOMMISSIONING**

# ACTIVITIES

## 1.1 OVERVIEW

One underground storage tank (UST), New Jersey Department of Environmental Protection (NJDEP) Registration No. 81515-27, was closed at Building 2537 at the Charles Wood area of U.S. Army Fort Monmouth Base, Fort Monmouth, New Jersey on May 27, 1997. Refer to site location map on Figure 1. This report presents the results of the Department of Public Works' (DPW) implementation of the UST Decommissioning/Closure Plan approved by the NJDEP on July 18, 1995. The UST was a steel 1,000-gallon tank containing No. 2 fuel oil.

Decommissioning activities for UST No. 81515-27 complied with all applicable Federal, State and Local laws and ordinances in effect at the date of decommissioning. These laws included but were not limited to N.J.A.C. 7:14B-1 et seq., N.J.A.C. 5:23-1 et seq., and Occupational Safety and Health Administration (OSHA) 1910.146 & 1910.120. All permits including but not limited to the NJDEP approved Decommissioning/Closure Plan was posted onsite for inspection. The decommissioning activities were conducted by DPW personnel who are registered and certified by the NJDEP for performing UST closure activities. Closure of UST No. 81515-27 proceeded under the approval of the NJDEP Bureau of Underground Storage Tanks (NJDEP-BUST). The NJDEP-BUST closure approval letter and signed Site Assessment Summary form for UST No. 81515-27 are included in Appendices A and B, respectively.

Based on inspecting the UST, field screening of subsurface soils and groundwater, and reviewing analytical results of collected soil samples and a groundwater sample, the DPW has concluded that no significant historical discharges are associated with the UST or associated piping.

This UST Closure and Site Investigation Report has been prepared by SMC Environmental Services Group, to assist the U. S. Army DPW in complying with the NJDEP-BUST regulations. The applicable NJDEP-BUST regulations at the date of closure were the *Interim Closure Requirements for Underground Storage Tank Systems* (N.J.A.C. 7:14B-1 et seq. October 1990 and revisions dated November 1, 1991).

This report was prepared using information collected at the time of closure. Section 1 of this UST Closure and Site Investigation Report provides a summary of the UST decommissioning activities. Section 2 of this report describes the site investigation activities. Conclusions and recommendations, including the results of the soil and groundwater sampling investigation, are presented in the final section of this report.

## 1.2 SITE DESCRIPTION

Building 2537 is located in the Charles Wood area of the Fort Monmouth Army Base. UST No. 81515-27 was located south of Building 2537 and appurtenant copper piping ran approximately thirty feet east from the excavation to Building 2537. A site map is provided on Figure 2.

### 1.2.1 Geological/Hydrogeological Setting

The following is a description of the geological/hydrogeological setting of the area surrounding Building 2537. Included is a description of the regional geology of the area surrounding Fort Monmouth as well as descriptions of the local geology and hydrogeology of the Charles Wood area.

#### Regional Geology

Monmouth County lies within the New Jersey Section of the Atlantic Coastal Plain physiographic province. The Main Post, Charles Wood, and the Evans areas are located in what may be referred to as the Outer Coastal Plain subprovince, or the Outer Lowlands.

In general, New Jersey Coastal Plain formations consist of a seaward-dipping wedge of unconsolidated deposits of clay, silt, and gravel. These formations typically strike northeast-southwest with a dip ranging from 10 to 60 feet per mile and were deposited on Precambrian and lower Paleozoic rocks (Zapeczka, 1989). These sediments, predominantly derived from deltaic, shallow marine, and continental shelf environments, date from Cretaceous through the Quaternary Periods. The mineralogy ranges from quartz to glauconite.

The formations record several major transgressive/regressive cycles and contain units which are generally thicker to the southeast and reflect a deeper water environment. Over 20 regional geologic units are present within the sediments of the Coastal Plain. Regressive, upward coarsening deposits are usually aquifers (e.g., Englishtown and Kirkwood Formations, and the Cohansey Sand) while the transgressive deposits act as confining units (e.g., the Merchantville, Marshalltown, and Navesink Formations). The individual thicknesses for these units vary greatly (i.e., from several feet to several hundred feet). The Coastal Plain deposits thicken to the southeast from the Fall Line to greater than 6,500 feet in Cape May County (Brown and Zapeczka, 1990).

#### Local Geology

Based on the regional geologic map (Jablonski, 1968), the Cretaceous age Red Bank and Tinton Sands outcrop at the Charles Wood area. The Red Bank sand conformably overlies the Navesink Formation and dips to the southeast at 35 feet per mile. The upper member (Shrewsbury) of the Red Bank sand is a yellowish-gray to reddish brown clayey, medium-to-coarse-grained sand that contains abundant rock fragments, minor mica and glauconite (Jablonski). The lower member (Sandy Hook) is a dark gray to black, medium-to-fine grained sand with abundant clay, mica, and glauconite.

The Tinton sand conformably overlies the Red Bank Sand and ranges from a clayey medium to very coarse grained feldspathic quartz and glauconite sand to a glauconitic coarse sand. The color varies from dark yellowish orange or light brown to moderate brown and from light olive to grayish olive. Glauconite may constitute 60 to 80 percent of the sand fraction in the upper part of the unit (Minard, 1969). The upper part of the Tinton is often highly oxidized and ironoxide encrusted (Minard).

Over the last 80 years, the natural topography of Fort Monmouth has been altered by excavation and filling activities by the military. Topographic elevations for the Charles Wood area range from 20 feet above mean seal level (MSL) to 71 feet above MSL.

### Hydrogeology

The water table aquifer in the Charles Wood area is identified as part of the "composite confining units", or minor aquifers. The minor aquifers include the Navesink formation, Red Bank Sand, Tinton Sand, Hornerstown Sand, Vincentown Formation, Manasquan Formation, Shark River Formation, Piney Point Formation, and the basal clay of the Kirkwood Formation.

Six well records for monitor wells installed at locations within the Charles Wood area in February 1981 were used for reference. The wells were completed to total depths ranging from 20 to 25 feet below ground surface (BGS). Water was encountered at depths ranging from 5 to 12 feet BGS.

The lithologic descriptions for these borings described deposits that were primarily fine to coarse, glauconitic sands, with traces of gravel, silt, and clay. These sediments are part of the Hornerstown Marl, from the Tertiary Period (Paleocene Series, approximately 58 to 66 Ma). According to Jablonski, wells drilled in the Red Bank and Tinton Sands may produce from 2 to 25 gallons per minute (gpm). Some well owners have reported acidic water that requires treatment to remove iron.

Shallow groundwater is locally influenced within the Charles Wood area by the following factors:

- tidal influence (based on proximity to the Atlantic Ocean, rivers, and tributaries)
- topography
- nature of the fill material within the Charles Wood area
- presence of clay and silt lenses in the natural overburden deposits
- local groundwater recharge areas (i.e., streams, lakes)

Due to the fluvial nature of the overburden deposits (i.e., sand and clay lenses), shallow groundwater flow direction is best determined on a case-by-case basis. Building 2537 is located approximately 200 feet south of an unnamed stream which runs from east to west through the Charles Wood area. Based on the Charles Wood area topography, the groundwater flow in the area of Building 2537 is anticipated to be to the northeast.



### **1.3 HEALTH AND SAFETY**

Before, during, and after all decommissioning activities, hazards at the work site which may have posed a threat to the Health and Safety of all personnel who were involved with, or were affected by, the decommissioning of the UST system were minimized. All areas, which posed, or may have been suspected to pose a vapor hazard were monitored by a qualified individual utilizing an organic vapor analyzer (OVA). The individual ascertained if the area was properly vented to render the area safe, as defined by OSHA.

### **1.4 REMOVAL OF UNDERGROUND STORAGE TANK**

#### **1.4.1 General Procedures**

- All underground obstructions (utilities, etc.) were identified by the contractor performing the closure prior to excavation activities.
- All activities were carried out with the greatest regard to safety and health and the safeguarding of the environment.
- All excavated soils were visually examined and screened with an OVA for evidence of contamination. Potentially contaminated soils were identified and logged during closure activities.
- Surface materials (i.e., asphalt, concrete, etc.) were excavated and staged separately from all soil and recycled in accordance with all applicable regulations and laws.
- A Sub-Surface Evaluator from the DPW was present during all site assessment activities.

#### **1.4.2 Underground Storage Tank Excavation and Cleaning**

Prior to UST decommissioning activities, surficial soil was removed to expose the UST and associated piping. The UST was removed from the excavation prior to cleaning because perched rain water was encountered at 2.0 feet bgs. The UST was staged on polyethylene sheeting and purged to remove any vapors prior to cutting a hole for proper cleaning. The UST was completely emptied of all liquids prior to removal from the site. Approximately 150 gallons of liquid from the UST and its associated piping were transported to the Fort Monmouth waste oil holding facility. Refer to Appendix C for a copy of the waste manifest.

One hole was observed during the inspection by the Sub-Surface Evaluator. Soils were screened visually and with an OVA for evidence of contamination. Stained soil was noted in the excavation area. Soil screening was also performed along the piping run associated with the UST closure. No contamination was noted anywhere along the piping length. Perched water was encountered at 3.0 feet bgs and no sheen was observed on the groundwater. See Figure 3 for a cross-sectional view of the excavated area.

## **1.5 UNDERGROUND STORAGE TANK TRANSPORTATION AND DISPOSAL**

The steel tank was transported to Mazza and Sons, Inc. for proper disposal. See Appendix D for the UST disposal certificate and Appendix G for photographs of the UST. The transportation of the UST was in compliance with all applicable regulations and laws.

The UST was labeled prior to transport with the following information:

- Site of origin
- Contact person
- NJDEP UST Facility ID number
- Name of transporter
- Destination site
- Date

## **1.6 MANAGEMENT OF EXCAVATED SOILS**

Based on visual observations, fifteen cubic yards of contaminated soil were removed from the excavation area. All potentially contaminated soils were stockpiled separately from other excavated material and were placed on and covered with polyethylene sheets. Potentially contaminated soils were transported to the soil staging area at Building 2624. Soils that did not exhibit signs of contamination were used as backfill following the removal of the UST. Perched water encountered did not exhibit a sheen.

## 2.0 SITE INVESTIGATION ACTIVITIES

### 2.1 OVERVIEW

The Site Investigation was managed and carried out by U.S. Army DPW personnel. All analyses were performed and reported by U.S. Army Fort Monmouth Environmental Laboratory, a NJDEP-certified testing laboratory. All sampling was performed under the direct supervision of a NJDEP Certified Sub-Surface Evaluator according to the methods described in the NJDEP *Field Sampling Procedures Manual* (1992). Sampling frequency and parameters analyzed complied with the NJDEP-BUST document *Interim Closure Requirements for Underground Storage Tank Systems* (October 1990 and revisions dated November 1, 1991) which was the applicable regulation at the date of the closure. All records of the Site Investigation activities are maintained by the Fort Monmouth DPW Environmental Office.

The following Parties participated in Closure and Site Investigation Activities:

- Subsurface Evaluator: Eugene W. Lesinski  
Employer: U.S. Army, Fort Monmouth  
Phone Number: (732) 532-0989  
NJDEP Certification No.: 0014537
- Analytical Laboratory: U.S. Army Fort Monmouth Environmental Laboratory  
Contact Person: Daniel K. Wright  
Phone Number: (732) 532-4359  
NJDEP Company Certification No.: 13461

### 2.2 FIELD SCREENING/MONITORING

Field screening was performed by a NJDEP Certified Sub-Surface Evaluator using an OVA and visual observations to identify potentially contaminated material. Soils were removed from the excavation until no evidence of contamination remained. Perched water encountered in the excavation did not exhibit a sheen.

### 2.3 SAMPLING

On May 28 and 29, 1997, following the removal of the UST, post-excavation soil samples A, B, C, D, E, F, G, H, I, and DUP C were collected from a total of nine locations of the UST excavation. Samples A and B which had OVA readings of 1 and 2 ppm, respectively were collected at 5.5 feet bgs. Samples C, D, E, F, and DUP C were collected along the sidewalls of the excavation floor at a depth of 5.5 feet bgs. Samples G and H were collected along the excavation floor at 6.5 feet bgs. Sample I was collected along the former piping length of the excavation, which was approximately seven (7) feet in length. The piping sample was collected at a depth of 1.0 feet bgs. All samples were analyzed for TPHC and total solids.

In addition, one groundwater sample, designated SW was collected from standing water in the

excavated area. The sample was analyzed for Total BTEX (Benzene #2, Toluene #2, Ethyl benzene #2, p+ m-Xylene #2, and o-Xylene #2).

U.S. Army personnel in accordance with the NJDEP Technical Requirements and the NJDEP *Field Sampling Procedures Manual* performed the site assessment. A summary of sampling activities including parameters analyzed is provided in Table 1. The post-excavation samples were collected using NJDEP *Field Sampling Procedures Manual* (1992) standard sampling procedures. Following sampling activities, the samples were chilled and delivered to U.S. Army Fort Monmouth Environmental Laboratory located in Fort Monmouth, New Jersey, for analysis.

## **3.0 CONCLUSIONS AND RECOMMENDATIONS**

### **3.1 SAMPLING RESULTS**

To evaluate soil conditions following removal of the UST and associated piping, post-excavation soil samples were collected on May 28 and 29, 1997 from a total of nine locations. All samples were analyzed for TPHC and total solids. The post-excavation sampling results were compared to the NJDEP residential direct contact total organic contaminants soil cleanup criteria of 10,000 mg/kg (N.J.A.C. 7:26D and revisions dated February 3, 1994). A summary of the analytical results and comparison to the NJDEP criteria is provided in Table 2 and the soil sampling locations are shown on Figure 4. The analytical data package is provided in Appendix E.

To evaluate the groundwater conditions, one groundwater sample was obtained on June 5, 1997 from standing water in the excavation. The sample was analyzed for total BTEX. The post-excavation sampling result was compared to the respective NJDEP groundwater standards for Class II-A Groundwater (N.J.A.C. 7:9-6). A summary of the analytical results and comparison to the NJDEP criteria is provided in Table 3. The analytical data package is provided in Appendix F.

All post-excavation soil samples collected on May 28 and 29, from the UST excavation and from below piping associated with the UST contained concentrations of TPHC below the NJDEP soil cleanup criteria. Samples contained levels of non-detectable levels of TPHC.

The post-excavation groundwater sample collected on June 5, 1997, from the UST excavation contained concentrations below Benzene # 2, Toluene # 2, Ethyl benzene #2, p+m-Xylene #2, and o-Xylene #2's respective criteria level. All results were non-detect.

### **3.2 CONCLUSIONS AND RECOMMENDATIONS**

The analytical results for all post-excavation soil samples collected from the UST closure excavation at Building 2537 were below the NJDEP soil cleanup criteria for total organic contaminants. The analytical results for the groundwater sample collected from the UST excavation at Building 2537 were below NJDEP groundwater quality standards.

Based on the post-excavation sampling results, soils with TPHC concentrations exceeding the NJDEP soil cleanup criteria for total organic contaminants of 10,000 mg/kg, do not exist in the former location of the UST or associated piping.

No further action is proposed in regard to the closure and site assessment of UST No. 81515-27 at Building 2537.

# TABLES

TABLE 2

POST-EXCAVATION SOIL SAMPLING RESULTS  
 BUILDING 2537, CHARLES WOOD AREA  
 FORT MONMOUTH, NEW JERSEY

Page 1 of 1

Sample ID/ Depth	Sample Laboratory ID	Sample Date	Analysis Date	Parameters	Method Detection Limit (mg/kg)	Compound of Concern	Result (mg/kg) *	NJDEP Soil Cleanup Criteria ** (mg/kg)	Exceeds Cleanup Criteria
A/2.5'	2600.01	5/28/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
B/2.5'	2600.02	5/28/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
C/2.5'	2600.03	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
D/2.5'	2600.04	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
E/2.5'	2600.05	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
F/2.5'	2600.06	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
G/2.5'	2600.07	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
H/2.5'	2600.08	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
I/1.0'	2600.09	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No
DUP C/2.5'	2600.10	5/29/97	6/4/97	Total Solid	--	--	86 %	--	--
				TPHC	20	yes	ND	10,000	No

## Note:

- \* Total Solid results are expressed as a percentage.  
 \*\* NJDEP Residential Direct Contact soil cleanup criteria for total organics  
 -- Not Applicable  
 ND Not detected above stated method detection limit  
 TPHC Total Petroleum Hydrocarbons

TPHC Total Petroleum Hydrocarbons

TABLE 3

POST-EXCAVATION GROUNDWATER SAMPLING RESULTS  
 BUILDING 2537, CHARLES WOOD AREA  
 FORT MONMOUTH, NEW JERSEY

Page 1 of 1



Sample ID/ Depth	Sample Laboratory ID	Sample Date	Analysis Date	Analytical Method Used	Method Detection Limit (ug/L)	Compound of Concern	Results (ug/L)	NJDEP Groundwater Standards* (ug/L)	Exceeds Cleanup Criteria
SW	2461.01	6/5/97		Benzene #2	0.51	yes	ND	1.0	--
				Toluene #2	0.73	yes	ND	1,000	--
				Ethyl benzene #2	1.14	yes	ND	700	--
				p + m-Xylene #2	2.53	yes	ND	40 <sup>(1)</sup>	--
				o-Xylene #2	1.92	yes	ND	40 <sup>(1)</sup>	--

Note:

- \* NJDEP Groundwater Standards for Class II-A Groundwater
- ND Not detected above stated method detection limit
- (1) Total Xylenes Standard used for p + m-Xylene #2 and o-Xylene #2.



## FIGURES




**LONG BRANCH, NJ**

40073-C8-TF-024

1954

PHOTOREVISED 1981

DMA 6164 I SE -SERIES V822



Quadrangle Location

**FIGURE 1**

**SITE LOCATION MAP**

Building 2537

Charles Wood Area

Fort Monmouth Army Base

Monmouth County, NJ



**SMC Environmental Services Group**  
Engineers, Managers, Scientists, & Planners  
Valley Forge, Pennsylvania

Mapped, edited and published by the Geological Survey

Scale: 1"=2,000'

Date: MARCH 1998





FIGURE 2  
SITE MAP  
BUILDING 2537  
FORT MONMOUTH ARMY BASE  
MONMOUTH COUNTY, NJ

 **SMC ENVIRONMENTAL  
SERVICES GROUP**  
Engineers, Managers, Scientists & Planners  
VALLEY FORGE, PA.

SCALE: 1"=100'      DATE: MARCH 1998

2537 2429 FG2




FIGURE 3  
 CROSS SECTIONAL VIEW  
 BUILDING 2537  
 FORT MONMOUTH ARMY BASE  
 MONMOUTH COUNTY, NJ




**SMC ENVIRONMENTAL  
 SERVICES GROUP**

Engineers, Managers, Scientists & Planners  
 VALLEY FORGE, PA

SCALE: NTS

DATE: MARCH 1998



**LEGEND**

- SOIL SAMPLE LOCATION (MAY 28, 1997)
- ▨ LIMIT OF EXCAVATION (MAY 27, 28, 1997)
- ▲ SOIL SAMPLE LOCATION (MAY 29, 1997)
- ▤ LIMIT OF EXCAVATION (MAY 29, 1997)

**FIGURE 4**  
**SOIL SAMPLING LOCATION MAP**  
**BUILDING 2537**  
**FORT MONMOUTH ARMY BASE**  
**MONMOUTH COUNTY, NJ**

**SMC ENVIRONMENTAL SERVICES GROUP**  
 Engineers, Managers, Scientists & Planners  
 VALLEY FORGE, PA

SCALE: 1"=10'      DATE: MARCH 1998

**NOTES:** 1. ALL RESULTS IN MG/KG.  
 2. SEE TABLE 2 FOR NJDEP SOIL CLEANUP CRITERIA  
 3. BGS = BELOW GROUND SURFACE

2537 2429 FIG4

**APPENDIX A**

**NJDEP-BUST CLOSURE APPROVAL**



# State of New Jersey

Department of Environmental Protection

Christine Todd Whitman  
Governor

Robert C. Shinn, Jr.  
Commissioner

**JUL 18 1995**

Mr. Dinker Desai  
SELFM-EH-EV  
Department of the Army  
Headquarters CECOM Fort Monmouth  
Fort Monmouth, NJ 077703-5000

Dear Mr. Desai:

Re: UST Closure Plan Approvals  
Fort Monmouth Army Base  
Fort Monmouth, Monmouth County

The NJDEP has reviewed the Underground Storage Tank Closure Plans for eight Number 2 Fuel Oil underground storage tanks located on the Fort Monmouth Army Base. Based on this review, the NJDEP hereby approves the closure plans as submitted on June 21, 1995 for the following tanks:

AREA	REGISTRATION NO.	BLDG NO.	UST NO.	TANK SAMP	LINE SAMP	REMOVAL DATE	REPORT DATE
CW - West	0081515	2504	16	4/1	1	7/24/95	11/24/95
CW - West	0081515	2529	20	4/1	1	7/25/95	11/29/95
CW - West	0081515	2535	25	4/1	1	7/26/95	11/28/95
CW - West	0081515	2536	26	4/1	2	7/28/95	11/30/95
CW - West	0081515	2537	27	4/1	1	8/1/95	12/4/95
CW - West	0081515	2561	31	4/1	2	8/2/95	12/4/95
CW - West	0081515	2532	22	4/1	1	6/5/95	10/6/95
CW - West	0081515	2533	23	4/1	2	6/7/95	10/9/95

Please advise me regarding the progress of tanks 22 and 23.

If you should have any questions or require any additional information, please feel free to contact me at (609) 633-1455.

Sincerely,

Ian R. Curtis, Case Manager  
Bureau of Federal Case Management

cc. Kevin Kratina, BUST

RPCEBFCM/FTMMTH27.IRC



State of New Jersey  
 Department of Environmental Protection and Energy  
 Division of Responsible Party Site Remediation  
 CN 028  
 Trenton, NJ 08625-0029

ATTN: UST Program  
 (609) 984-3156

For State Use Only

Date Rec'd. \_\_\_\_\_  
 Auth. \_\_\_\_\_  
 Routing \_\_\_\_\_  
 UST NO. \_\_\_\_\_

STANDARD REPORTING FORM  
 for reporting activities at an UST facility:

- |  |   |
|--|---|
| <input checked="" type="checkbox"/> General Facility Information Changes | <input type="checkbox"/> Sale or Transfer         |
| <input checked="" type="checkbox"/> Closure (Abandonment or Removal)     | <input type="checkbox"/> Substantial Modification |
| <input type="checkbox"/> Temporary Closure                               | <input type="checkbox"/> Financial Responsibility |
| <input type="checkbox"/> Change in Service                               | <input type="checkbox"/> Address Change Only      |

Check ONLY One Type of Activity - Complete Form For That Activity

(More than one tank can be listed per activity)

\*\*\* NOTE \*\*\* ALL NEW tank installations at existing registered facilities must submit a Registration Questionnaire for the new tanks.

Answer questions 1 through 5 and others as applicable.

1. Company name and address (as it appears on registration questionnaire):

U.S. ARMY - FORT MONMOUTH  
DPW - BUILDING 173  
FORT MONMOUTH NJ 07703  
ATTN: EUGENE W. LESINSKI

2. Facility name and location (if different from above):

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

3. Contact person for this activity:

GENE LESINSKI  
 Telephone Number: (908) 532-0989

4. The identification number of the affected tank as it appears in Question Number 12 on the Registration Questionnaire:

BLDG 2537 27

5. Registration Number (if known):

UST - 0081515

6. For GENERAL FACILITY INFORMATION changes (address, telephone, contact person, etc. - supply NEW information only):

a. Facility name: \_\_\_\_\_

b. Facility location: \_\_\_\_\_

c. Owner's mailing address: \_\_\_\_\_

\_\_\_\_\_  
 \_\_\_\_\_ NJ \_\_\_\_\_

d. Block: \_\_\_\_\_ Lot: \_\_\_\_\_

e. Contact person (facility operator): \_\_\_\_\_

f. Contact telephone number: (\_\_\_\_\_) \_\_\_\_\_

g. Other (Specify): \_\_\_\_\_

(OVER)



7 For CLOSURE (abandonment or removal - check all that apply):

a.  Abandonment Date:   /  /   Case No:                   

Attach the necessary implementation schedule (3 copies) and all documents needed for abandonment per N.J.A.C. 7:14B-9.1 (d).

b.  Removal Date: 5/27/97 Case No. 97-5-27-1421-04

Attach the necessary implementation schedule (3 copies).

8. For CHANGES IN HAZARDOUS SUBSTANCES STORED (check all that apply):

a.  Temporary Closure (12 month maximum time - see N.J.A.C. 7:14B-9.1(b)). Remove all hazardous substances; leave tank in place.

b.  Change in service from a regulated substance to a non-regulated substance. Tank must be cleaned and site assessment performed per N.J.A.C. 7:14B-9.1(e).

c.  Changes in service from one regulated hazardous substance to another regulated hazardous substance.

Tank No. _____	Old _____	New _____
Tank No. _____	Old _____	New _____
Tank No. _____	Old _____	New _____

(Attach additional sheets if more space is needed)

9. For TRANSFER OF OWNERSHIP: Effective Date:   /  /  

a. New Owner (operator) \_\_\_\_\_

b. New Facility Name \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_ NJ \_\_\_\_\_

\_\_\_\_\_ County \_\_\_\_\_

c. Closing Attorney \_\_\_\_\_ Title: ( ) \_\_\_\_\_

10. For SUBSTANTIAL MODIFICATIONS (to include any retrofitted activity - e.g. the addition of spill/overflow protection, monitoring systems, cathodic protection, etc.):

a. Type of Modification \_\_\_\_\_ Date:   /  /  

b. \* NOTE \* Substantial modifications require a permit under N.J.A.C. 7:14B-10.

11. For changes in FINANCIAL RESPONSIBILITY to (check appropriate changes and attach copies of new information):

- a. Policy Type:
- b. Policy Number:
- c. Other:
- d. Company/Carrier:
- e. Expiration Date:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(Specify)

NOTE: ALL appropriate and applicable permits, licenses and certificates required by the above activity(ies) from any local, state and/or federal agencies must be obtained separately from this notification.

CERTIFICATION

\*\*\*This registration form shall be signed by the highest ranking individual at the facility with overall responsibility for that facility (N.J.A.C. 7:14B-23 (a) 1).\*\*\*

"I certify under penalty of law that the information provided in this document is true, accurate and complete. I am aware that there are significant civil and criminal penalties for submitting false, inaccurate or incomplete information, including fines and/or imprisonment."

Signature: 

Name (print or type): JAMES OTT

Title: DIRECTOR - DEPT OF PUBLIC WORKS Date: 6-17-97

**APPENDIX B**  
**SITE ASSESSMENT SUMMARY**

**FOR STATE USE ONLY**

**UST#**

Date Rec'd

**TMS #**

Staff

**STATE OF NEW JERSEY  
DEPARTMENT OF ENVIRONMENTAL PROTECTION**

Division of Responsible Party Site Remediation

CN 029

TRENTON, N.J. 08625-0028

Tel. # 609-984-3156

Fax.# 609-292-5604

Scott A. Weiner  
Commissioner

Karl J. Delaney  
Director

**UNDERGROUND STORAGE TANK  
SITE ASSESSMENT SUMMARY**

*Under the provisions of the Underground Storage  
of Hazardous Substances Act  
in accordance with N.J.A.C. 7:14B*

This Summary form shall be used by all owners and operators of Underground Storage Tank Systems (USTS) who have either reported a release and are subject to the site assessment requirements of N.J.A.C. 7:14B-8.2 or who have closed USTS pursuant to N.J.A.C. 7:14B-9.1 et seq. and are subject to the site assessment requirements of N.J.A.C. 7:14B-9.2 and 9.3.

**INSTRUCTIONS:**

- ◆ Please print legibly or type.
- ◆ Fill in all applicable blanks. This form will require various attachments in order to complete the Summary. The technical guidance document, Interim Closure Requirements for UST's, explains the regulatory (and technical) requirements for closure and the Scope of Work, Investigation and Corrective Action Requirements for Discharges from Underground Storage Tanks and Piping Systems explains the regulatory (and technical) requirements for corrective action.
- ◆ Return one original of the form and all required attachments to the above address.
- ◆ Attach a scaled site diagram of the subject facility which shows the information specified in Item IV B of this form.
- ◆ Explain any "No" or "N/A" response on a separate sheet.

Date of Submission: 7/27/98

Building No. 2537 UST No. 81515-27

0192477-1

**Facility Registration #**

**1. FACILITY NAME AND ADDRESS:**

U.S. Army Fort Monmouth New Jersey

Directorate of Engineering and Housing Building 167

Fort Monmouth, New Jersey 07703 County Monmouth

Telephone No. 732-532-6224

**OWNER'S NAME AND ADDRESS, if different from above.**

Telephone No.

II. DISCHARGE REPORTING REQUIREMENTS

A. Was contamination found?  Yes  No If Yes, Case No. 97-5-27-1421-04  
(Note: All discharges must be reported to the Environmental Action Hotline (609) 292-7172)

B. The substance(s) discharged was (were) No. 2 Fuel Oil

C. Have any vapor hazards been mitigated?  Yes  No  N/A

III. DECOMMISSIONING OF TANK SYSTEMS Closure approval No. July 18, 1995 letter

The site assessment requirements associated with tank decommissioning are explained in the Technical Guidance Document, Interim Closure Requirements for UST's, Section V. A.-D. Attach complete documentation of the methods used and the results obtained for each of the steps of tank decommissioning used. Please include a site map which shows the locations of all samples and borings, the location of all tanks and piping runs at the facility at the beginning of the tank closure operation and annotated to differentiate the status of all tanks and piping (e.g., removed, abandoned, temporarily closed, etc.). The same site map can be used to document other parts of the site assessment requirements, if it is properly and legibly annotated.

IV. SITE ASSESSMENT REQUIREMENTS

A. Excavated Soil

Any evidence of contamination in excavated soil will require that the soil be classified as either Hazardous Waste or Non-Hazardous Waste. Please include all required documentation of compliance with the requirements for handling contaminated excavated soil (if any was present) as explained in the technical guidance documents for closure and corrective action. Describe the amount of soil removed, its classification and disposal location.

B. Scaled Site Diagrams

1. Scaled site diagrams must be attached which include the following information:

- a. North arrow and scale
- b. The locations of the ground water monitoring wells
- c. Location and depth of each soil sample and boring
- d. All major surface and subsurface structures and utilities
- e. Approximate property boundaries
- f. All existing or closed underground storage tank systems, including appurtenant piping
- g. A cross-sectional view indicating depth of tank, stratigraphy and location of water table
- h. Locations of surface water bodies

C. Soil samples and borings (check appropriate answer)

1. Were soil samples taken from the excavation as prescribed?  Yes  No  N/A
2. Were soil borings taken at the tank system closure site as prescribed?  Yes  No  N/A
3. Attach the analytical results in tabular form and include the following information about each sample
  - a. Customer sample number (keyed to the site map)
  - b. The depth of the soil sample
  - c. Soil boring logs
  - d. Method detection limit of the method used
  - e. QA/QC information as required

D. Ground Water Monitoring

1. Number of ground water monitoring wells installed 0
2. Attach the analytical results of the ground water samples in tabular form. Include the following information for each sample from each well:
  - a. Site diagram number for each well installed
  - b. Depth of ground water surface
  - c. Depth of screened interval
  - d. Method detection limit of the method used
  - e. Well logs
  - f. Well permit numbers
  - g. QA/QC Information as required

V. SOIL CONTAMINATION

- A. Was soil contamination found?  Yes  No  
If "Yes," please answer Question B-E  
If "No," please answer Question B
- B. The highest soil contamination still remaining in the ground has been determined to be:
  1. N/A ppb total BTEX, N/A ppb total non-targeted VOC
  2. N/A ppb total B/N, N/A ppb total non-targeted B/N
  3. ND ppm TPHC
  4. N/A ppb N/A (for non-petroleum substance)
- C. Remediation of free product contaminated soils
  1. All free product contaminated soil on the property boundaries and above the water table are believed
  2. Free product contaminated soils are suspected to exist below the water table.  Yes  No
  3. Free product contaminated soils are suspected to exist off the property boundaries.  Yes  No
- D. Was the vertical and horizontal extent of contamination determined?  Yes  No   
N/A
- E. Does soil contamination intersect ground water?  Yes  No  N/A

VI. GROUND WATER CONTAMINATION

- A. Was ground water contamination found?  Yes  No  
If "Yes," please answer Questions B-G.  
If "No," please answer only Question B.
- B. The highest ground water contamination at any 1 sampling location and at any 1 sampling event to date has been determined to be: N/A
  1. ND ppb total BTEX, ND ppb total non-targeted VOC
  2. N/A ppb total B/N, N/A ppb total non-targeted B/N
  3. N/A ppb total MTBE, N/A ppb total TBA
  4. N/A ppb N/A (for non-petroleum substance)
  5. greatest thickness of separate phase product found N/A
  6. separate phase product has been delineated  Yes  No  N/A
- C. Result (s) of well search

UST-014  
2/91

1. A well search (including a review of manual well records) indicates that private, municipal or commercial wells do exist within the distances specified in the Scope of Work.  Yes  No  N/A

2. The number of these wells identified is \_\_\_\_\_.

D. Proximity of wells and contaminant plume

1. The shallowest depth of any well noted in the well search which may be in the horizontal or vertical potential path(s) of the contaminant plume(s) is \_\_\_\_\_ feet below grade (consideration has been given for the effects of pumping, subsurface structures, etc. on the direction(s) of contaminant migration). This well is \_\_\_\_\_ feet from the source and its screening begins at a depth of \_\_\_\_\_ feet.
2. The shallowest depth to the top of the well screen for any well in the potential path of the plume(s) (as described in D1 above) is \_\_\_\_\_ feet below grade. This well is located \_\_\_\_\_ feet from the source.
3. The closest horizontal distance of a private, commercial, or municipal well in the potential path of the plume (as determined in D1) is \_\_\_\_\_ feet from the source. This well is \_\_\_\_\_ feet deep and screening begins at a depth of \_\_\_\_\_ feet.

E. A plan for separate phase product recovery has been included.  Yes  No  N/A

F. A ground water contour map has been submitted which includes the ground water elevations for each well.  Yes  No  N/A

G. Delineation of contamination

1. The ground water contaminants have been delineated to MCLs or lower values at the property boundaries.  Yes  No
2. The plume is suspected to continue off the property at concentrations greater than MCLs.  Yes  No
3. Off property access (circle one): is being sought has been approved has been denied

VII. SITE ASSESSMENT CERTIFICATION [preparer of site assessment plan - N.J.A.C. 7:14B-8.3(b) & 9.5(a)3]

The person signing this certification as the "Qualified Ground Water Consultant" (as defined in N.J.A.C. 7:14B-1.6) responsible for the design and implementation of the site assessment plan as specified in N.J.A.C. 7:14B-8.3(a) & 9.2(b)2, must supply the name of the certifying organization and certification number.

*"I certify under penalty of law that the information provided in this document is true, accurate, and complete and was obtained by procedures in compliance with N.J.A.C. 7:14B-8 and 9. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."*

NAME (Print or Type) Eugene Lesinsky

SIGNATURE SEE ATTACHED SUB-SURFACE EVALUATOR LOG

COMPANY NAME U.S. Army Fort Monmouth DATE NA

(Preparer of Site Assessment Plan)

CERTIFYING ORGANIZATION NJDEP

CERTIFYING NUMBER 2056

VIII. TANK DECOMMISSIONING CERTIFICATION [person performing tank decommissioning portion of closure

UST-014  
2/91

plan - N.J.A.C. 7:14B-9.5(a)4]

*"I certify under penalty of law that tank decommissioning activities were performed in compliance with N.J.A.C. 7:14B-9.2(b)3. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."*

NAME (Print or Type) SAME AS SITE ASSESSMENT SIGNATURE \_\_\_\_\_

COMPANY NAME \_\_\_\_\_ DATE \_\_\_\_\_  
(Performer of Tank Decommissioning)

IX. CERTIFICATIONS BY THE RESPONSIBLE PARTY(IES) OF THE FACILITIES

A. The following certification shall be signed by the highest ranking individual with overall responsibility for that facility [N.J.A.C. 7:14B-2.3(c)1].

*"I certify under penalty of law that the information provided in this document is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."*

NAME (Print or Type) James Ott SIGNATURE 

COMPANY NAME U.S. Army Fort Monmouth DATE 7/27/98

B. The following certification shall be signed as follows [according to the requirements of N.J.A.C. 7:14B-2.3(C)2]:

1. For a corporation, by a principal executive officer of at least the level of vice president.
2. For a partnership or sole proprietorship, by a general partner or the proprietor, respectively; or
3. For a municipality, State, Federal or other public agency by either the principal executive officer or ranking elected official.
4. In cases where the highest ranking corporate partnership, governmental officer or official at the facility as required in A above is the same person as the official required to certify in B, only the certification in A need to be made. In all other cases, the certifications of A and B shall be made.

*"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this application and all attached documents, and that based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment."*

NAME (Print or Type) \_\_\_\_\_ SIGNATURE \_\_\_\_\_

COMPANY NAME \_\_\_\_\_ DATE \_\_\_\_\_

**I ARMY, SELFM-PW-E**  
**DAILY UST SUBSURFACE REMOVAL LOG**

BLDG.#: 2537 REG.#: 0081515 - 27 CLOSURE#: NJDEP LTR 18 JUL 95  
 DATE: 5-27-97 TOA: 1330 TOD: 1430  
 GOV. SSE: LESINSKI NJDEP CERT.#: 8914537  
 REMOVAL CONTRACTOR: SAI Inc. TVS  
 CLOSURE SUPERVISOR: GARY IAMELLO NJDEP CERT.#: —  
 WEATHER: SUNNY - 65° F

ACTIVITY	YES / NO
THE SUPERVISOR (CLOSURE CERT.) WAS ON-SITE DURING ALL CLOSURE RELATED ACTIVITIES	Y
THE SSE WAS ON-SITE DURING UST REMOVAL AND SITE SCREENING AND SAMPLING ACTIVITIES	Y
ALL ON-SITE PERSONNEL HAD TRAINING IAW ALL SAFETY REQUIREMENTS (E.G. 29CFR)	Y
A CONFINED ENTRY PERMIT WAS COMPLETED AND POSTED ON-SITE BY THE CONTRACTOR	N/A
THE UST WAS PLACED ONTO PLASTIC, SCRAPED OFF, INSPECTED FOR HOLES AND PHOTOGRAPHED	Y
A DISCHARGE WAS REPORTED TO THE NJDEP (609-292-7172), CASE# <u>97-5-27-1421-04</u>	Y
PHOTOS HAVE UST#, BLDG. #, DATE, TIME, NAME OF SSE AND DESCR. WRITTEN ON BACK	Y
<del>RECEIVED</del> GROUNDWATER WAS ENCOUNTERED AT <u>6</u> FEET BG, A SHEEN (WAS <u>WAS NOT</u> ) OBSERVED ON GW	Y
IF OVA/Hnu WAS USED: WAS IT CAL. AND FOUND TO BE OPERATIONAL (cal. data on COC)	N/A
IF SAMPLES WERE TAKEN: COC, SCALED SITE MAP (VERT. SOIL HORIZONS AND PLOT PLAN)	N/A
ALL SAMPLE COLLECTION ACTIVITIES WERE AS DESCRIBED IN THE NJDEP FSPM, 1992	N/A
ALL SAMPLING WAS BIASED TOWARD HIGHEST OVA/FID RECORDED SITES IAW 7:26E-3.6 <u>et seq.</u>	N/A
ALL PETROL. CONT. SOILS WERE SECURED FROM THE WEATHER BY CLOSE OF BUSINESS TODAY	Y
THE SSE AUTHORIZED BACKFILLING THE EXCAVATION (STONE TO 1" ABOVE GROUNDWATER)	N/A
ADDITIONAL NOTES WERE TAKEN AND ARE RECORDED ON THE BACK OF THIS FORM	N
THE FOLLOWING DOCUMENTS WERE ADDED TO THE PROJECT FOLDER TODAY: (CIRCLE EACH) SCRAP TICKET, CSE PERMIT, ACCIDENT REPORT, HAZ. WASTE MANIFEST, DAILY UST CLOSURE LOG, SCALED SITE MAP (SAMPLING), <del>SEP</del> -CLOSURE, CHAIN OF CUSTODY, SOIL ANALYTICAL RESULTS, CLEAN FILL TICKETS (IN YDS <sup>3</sup> ), <u>PHOTOGRAPHS</u> (UST EXCAVATION, SAMPLING POINTS)	Y

**CHECK ALL BOXES. LEAVE NO BLANKS**

I certify under penalty of law that tank decommissioning activities were performed in compliance with N.J.A.C. 7:14B-9.2(b)3 and 7:26 et seq.. I am aware that there are significant penalties for submitting false, inaccurate, or incomplete information, including fines and/or imprisonment.

SIGNATURE: \_\_\_\_\_ DATE: 5-27-97



**APPENDIX C**  
**WASTE MANIFEST**



RD. 1, BOX 5A - OLD BRIDGE, NJ 08857

NON-HAZARDOUS WASTE MANIFEST

1. Generator's US EPA ID No.

NJ221-00-209-780-7-852

Manifest Document No.

2. Page 1 of 1

NHZ 004852

3. Generator's Name and Mailing Address  
U.S. Army Communications Electronics Command  
James Wood Hall, c/o S. Fallon Bldg. 173  
Attn: SELF M - PW - EV Fort Monmouth NJ 07703

4. Generator's Phone (908) 532-6223

2537

5. Transporter 1 Company Name  
LIONETTI OIL RECOVERY CO INC

N J D 0 8 4 0 4 4 0 6 4

A. Transporter's Phone  
908-721-0900

7. Transporter 2 Company Name

8. US EPA ID Number

B. Transporter's Phone

9. Designated Facility Name and Site Address  
LIONETTI OIL RECOVERY CO INC DBA LORCO PETROLEUM SVCS  
RUNYON & CHEESEWAKE RDS  
OLD BRIDGE, NJ 08857

N J D 0 8 4 0 4 4 0 6 4

C. Facility's Phone  
908 721-0900

11. Waste Shipping Name and Description

12. Containers  
No. Type

13. Total Quantity

14. Unit Wt/Vol

a. PETROLEUM OIL (PETROLEUM OIL)  
COMBUSTIBLE LIQUID UN1270 PGIII

0 0 1 T T

X X 3.75

G

b.

c.

d.

D. Additional Descriptions for Materials Listed Above  
T, L PETROLEUM OIL 50 %  
WATER 50 %

E. Handling Codes for Wastes Listed Above  
T04 FILTRATION

15. Special Handling Instructions and Additional Information  
24 HR EMERGENCY RESPONSE# (908) 721-0900  
DECAL# 73632 ERG# 128 DEXSIL TEST KIT RESULTS NA PPM  
MANIFEST USED FOR TRACKING PURPOSES ONLY

16. GENERATOR'S CERTIFICATION: I certify the materials described above on this manifest are not subject to federal regulations for reporting proper disposal of Hazardous Waste.

Printed/Typed Name  
EUGENE W LESINSKI

Signature  
*Eugene W Lesinski*

Month Day Year  
06 03 97

17. Transporter 1 Acknowledgement of Receipt of Materials

Printed/Typed Name  
Richard D D'Arcenzo

Signature  
*Richard D'Arcenzo*

Month Day Year  
06 03 97

18. Transporter 2 Acknowledgement of Receipt of Materials

Printed/Typed Name

Signature

Month Day Year

19. Discrepancy Indication Space

20. Facility Owner or Operator: Certification of receipt of waste materials covered by this manifest except as noted in Item 19.

Printed/Typed Name  
PAUL J. AMADIO

Signature  
*Paul J. Amadio*

Month Day Year  
06 03 97

ORIGINAL - RETURN TO GENERATOR

GENERATOR

TRANSPORTER

FACILITY

**APPENDIX D**  
**UST DISPOSAL CERTIFICATE**



**APPENDIX E**

**SOIL ANALYTICAL DATA PACKAGE**


US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY  
NJDEPE # 13461

REPORT OF ANALYSIS

Client: U.S. Army  
DPW, SELFM-PW-EV  
Bldg. 173  
Ft. Monmouth, NJ 07703

Project: Total Petroleum Hydrocarbons  
96-1262  
Bldg. 2537  
UST

Project # 2600  
Date Rec. 05/29/97  
Date Compl. 06/04/97  
Released by:



Daniel K. Wright  
Laboratory Director

## Table of Contents

<u>Section</u>	<u>Pages</u>
Cover Sheet	1
Table of Contents	2
Method Summary	3
Conformance/Non-Conformance	4
Chain of Custody	5
Results Summary	6
Initial Calibration Summary	7
Continuing Calibration Summary	8-9
Surrogate Results Summary	10
MS/MSD Results Summary	11
Quality Control Spike Summary	12
Raw Sample Data	13-32
Laboratory Deliverable Checklist	33

## **Method Summary**

### **NJDEP Method OQA-QAM-025-10/97**

#### **Gas Chromatographic Determination of Total Petroleum Hydrocarbons in Soil**

Fifteen grams (15g)(wet weight) of a soil sample is added to a 125 mL acid cleaned, solvent rinsed, capped Erlenmeyer flask. 15g anhydrous sodium sulfate is added to dry sample. Surrogate standard spiking solution is then added to the flask.

Twenty five milliliters(25mL) Methylene Chloride is added to the flask and it is secured on a gyrotory shaker table. The agitation rate is set to 400rpm and the sample is shaken for 30 minutes. The flask is the removed from the table and the particulate matter is allowed to settle. The extract is transferred to a Teflon capped vial. A second 25mL of Methylene Chloride is added to the flask and shaken for an additional 30 minutes. The flask is again removed and allowed to settle. The extracts are combined in the vial then transferred to a 1mL autosampler vial.

The extract is then injected directly into a GC-FID for analysis. The sample is analyzed for petroleum hydrocarbons covering a range of C8-C42 including pristane and phytane. Total Petroleum Hydrocarbon concentration is determined by integrating between 5 minutes and 22 minutes. The baseline is established by starting the integration after the end of the solvent peak and stopping after the last peak.

The final concentration of Total Petroleum Hydrocarbons is calculated using percent solid, sample weight and concentration.




PHC Conformance/Non-conformance Summary Report

	<u>No</u>	<u>Yes</u>
1. Method Detection Limits provided.	—	✓
2. Method Blank Contamination - If yes, list the sample and the corresponding concentrations in each blank. _____ _____	✓	—
3. Matrix Spike Results Summary Meet Criteria. (If not met, list the sample and corresponding recovery which falls outside the acceptable range). _____ _____	—	✓
4. Duplicate Results Summary Meet Criteria. _____ (If not met, list the sample and corresponding recovery which falls outside the acceptable range). _____ _____	—	✓
5. IR Spectra submitted for standards, blanks, & samples	—	NA
6. Chromatograms submitted for standards, blanks, and samples if GC fingerprinting was conducted.	—	✓
7. Analysis holding time met. (If not met, list number of days exceeded for each sample) _____ _____	—	✓
Additional Comments: _____ _____ _____		

Laboratory Authentication Statement

I certify under penalty of law, where applicable, that this laboratory meets the Laboratory Performance Standards and Quality Control requirements specified in N.J.A.C. 7:18 and 40 CFR Part 136 for Water and Wastewater Analyses and SW 846 for Solid Waste Analysis. I have personally examined the information contained in this report, and to the best of my knowledge, I believe that the submitted information is true, accurate, complete, and meets the above referenced standards where applicable. I am aware that there are significant penalties for purposefully submitting falsified information, including the possibility of a fine and imprisonment.

  
\_\_\_\_\_  
Daniel K. Wright  
Laboratory Manager



# Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703  
 Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil  
 NJDEP Certification #13461

## Chain of Custody Record

Customer: <b>GENE LESINSKI - DAW</b>		Project No: <b>96-1262</b>		Analysis Parameters						Comments:	
Phone #: <b>20989</b>		Location: <b>PISTOL B. 2537 RANGE</b>		TPHC	% SOLIDS	MUNSELL	VOA+5	TO BE DETERMINED	OVA	* = SAMPLES KEPT BELOW 4°C.	
( ) DERA (X) OMA ( ) Other:		Samplers Name / Company: <b>GARY DIMARTINS / TUS</b>								Sample #	
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles						
2600 .01	2537-A	5-28-97	1432	SOIL	2	X	X	X	X	1	5.5' DEPTH *
.02	2537-B	↓	1457		↓					2	↓
.03	2537-C	5-28-97	0930		1					ND	SIDEWALL @ 5.5'
.04	2537-D		0938							ND	
.05	2537-E		1133							ND	
.06	2537-F		1139							ND	
.07	2537-G		1323							ND	EXC FLOOR @ 6.5'
.08	2537-H		1329							ND	↓
.09	2537-I		1305							ND	Piping Run @ 1.0'
.10	2537-DUP									-	FIELD DUPLICATE
.11	2537-FB	5-28-97	1505	AQ	2		X			-	FIELD BLANK ✓, Hc
NOTE: OVA (#A52114) CALIBRATED w/ 95ppm CH4 & ZERO (O) AIR @ 1400 HRS. ON 5/28/97 BY G. DIMARTINS. OVA CALIBRATION CHECKED @ 0915 HRS. ON 5/29/97.											
Relinquished by (signature): <i>[Signature]</i>		Date/Time: 5-29-97 1530		Received by (signature): <i>[Signature]</i>		Date/Time: 5-29-97		Relinquished by (signature):		Date/Time:	
Relinquished by (signature):		Date/Time:		Received by (signature):		Date/Time:		Relinquished by (signature):		Date/Time:	
Report Type: ( ) Full, (X) Reduced, ( ) Standard, ( ) Screen / non-certified						Remarks: <b>DEDICATED SAMPLING TOOLS USED.</b>					
Turnaround time: ( ) Standard 4 wks, (X) Rush <b>3</b> Days, ( ) ASAP Verbal _____ Hrs.											



Response Factor Report TC, FID

Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997

Calibration Files

1 =T01476.D 2 =T01475.D 3 =T01474.D  
 4 =T01473.D 5 =T01472.D

Compound		1	2	3	4	5	Avg		%RSD
1) s	o-terphenyl	2.139	2.095	2.016	2.018	1.952	2.044	E4	3.60
2) t	tphc	3.165	2.484	2.078	1.919	1.820	2.293	E4	23.94

Evaluate Continuing Calibration Report

Data File : C:\HPCHEM\1\DATA\970602\T01510.D Vial: 3  
 Acq On : 3 Jun 97 6:56 pm Operator: Skelton  
 Sample : 50 PPM STD Inst : FID/TCD  
 Misc : Multiplr: 1.00  
 IntFile : autoint1.e

Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min  
 Max. RRF Dev : 25% Max. Rel. Area : 150%

Compound	AvgRF	CCRF	%Dev	Area%	Dev(min)
1 s o-terphenyl	20.439	23.147 E3	-13.2	108	0.00
2 t tphc	22.932	19.649 E3	14.3	95	0.00

Evaluation Continuing Calibration Report

Data File : C:\HPCHEM\1\DATA\970602\T01521.D Vial: 3  
 Acq On : 4 Jun 97 3:57 am Operator: Skelton  
 Sample : 50 PPM STD Inst : FID/TCD  
 Misc : Multiplr: 1.00  
 IntFile : autoint1.e

Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Multiple Level Calibration

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min  
 Max. RRF Dev : 25% Max. Rel. Area : 150%

Compound	AvgRF	CCRF	%Dev	Area%	Dev(min)
1 s o-terphenyl	20.439	24.059 E3	-17.7	112	0.00
2 t tphc	22.932	20.323 E3	11.4	98	0.00



Report of Analysis  
U.S. Army, Fort Monmouth Environmental Laboratory  
NJDEP Certification # 13461

**Matrix Spike Recovery Report**

Lab. ID #: 2600

Location #: B2537

Sample	Spike Amount Added (ppm)	Sample Amount (ppm)	Matrix Spike Amount (ppm)	Percent Recovery	QC Limits %
2600.10MS	630	0.00	763.77	121.23	75-125
2600.10MSD	630	0.00	693.50	110.08	75-125

RPD	9.64	20.00
-----	------	-------

6/4/97



Quantitation Report (NOT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01517.D Vial: 46  
 Acq On : 4 Jun 97 12:39 am Operator: Skelton  
 Sample : 2600.01 Inst : FID/TCD  
 Misc : 2537-A Multiplr: 1.00  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:22 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	230369	11.271 mg/L m
Spiked Amount 10.000		Recovery =	112.71%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L

Quantitation Report


Data File : C:\HPCHEM\1\DATA\970602\T01517.D  
Acq On : 4 Jun 97 12:39 am  
Sample : 2600.01  
Misc : 2537-A  
IntFile : autoint1.e

Vial: 46  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Time: Jun 4 9:22 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01518.D Vial: 47  
 Acq On : 4 Jun 97 1:33 am Operator: Skelton  
 Sample : 2600.02 Inst : FID/TCD  
 Misc : 2537-B Multiplr: 1.00  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	228229	11.167 mg/L m
Spiked Amount 10.000		Recovery =	111.67%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L

Quantitation Report


Data File : C:\HPCHEM\1\DATA\970602\T01518.D  
Acq On : 4 Jun 97 1:33 am  
Sample : 2600.02  
Misc : 2537-B  
IntFile : autoint1.e

Vial: 47  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (T Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01519.D Vial: 48  
 Acq On : 4 Jun 97 2:17 am Operator: Skelton  
 Sample : 2600.03 Inst : FID/TCD  
 Misc : 2537-C Multiplr: 1.00  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
-----			
System Monitoring Compounds			
1) s o-terphenyl	13.68	206784	10.117 mg/L m
Spiked Amount 10.000		Recovery =	101.17%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L


Quantitation Report

Data File : C:\HPCHEM\1\DATA\970602\T01519.D  
Acq On : 4 Jun 97 2:17 am  
Sample : 2600.03  
Misc : 2537-C  
IntFile : autoint1.e  
Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Vial: 48  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (NOT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01520.D Vial: 49  
 Acq On : 4 Jun 97 3:09 am Operator: Skelton  
 Sample : 2600.04 Inst : FID/TCD  
 Misc : 2537-D Multiplr: 1.00  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	238154	11.652 mg/L m
Spiked Amount 10.000		Recovery =	116.52%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L


Quantitation Report

Data File : C:\HPCHEM\1\DATA\970602\T01520.D  
Acq On : 4 Jun 97 3:09 am  
Sample : 2600.04  
Misc : 2537-D  
IntFile : autoint1.e  
Quant Time: Jun 4 9:23 1997 Quant Results File: TPH7.RES

Vial: 49  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm





Quantitation Report (Not Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01522.D  
 Acq On : 4 Jun 97 4:41 am  
 Sample : 2600.05  
 Misc : 2537-E  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:24 1997 Quant Results File: TPH7.RES

Vial: 51  
 Operator: Skelton  
 Inst : FID/TCD  
 Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	209151	10.233 mg/L m
Spiked Amount 10.000		Recovery =	102.33%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L

Quantitation Report


Data File : C:\HPCHEM\1\DATA\970602\T01522.D  
Acq On : 4 Jun 97 4:41 am  
Sample : 2600.05  
Misc : 2537-E  
IntFile : autoint1.e  
Quant Time: Jun 4 9:24 1997

Vial: 51  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01523.D  
 Acq On : 4 Jun 97 5:33 am  
 Sample : 2600.06  
 Misc : 2537-F  
 IntFile : autoint1.e

Vial: 52  
 Operator: Skelton  
 Inst : FID/TCD  
 Multiplr: 1.00

Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	230087	11.257 mg/L m
Spiked Amount 10.000		Recovery =	112.57%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L


Quantitation Report

Data File : C:\HPCHEM\1\DATA\970602\T01523.D  
Acq On : 4 Jun 97 5:33 am  
Sample : 2600.06  
Misc : 2537-F  
IntFile : autoint1.e  
Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Vial: 52  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



24

Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01524.D  
 Acq On : 4 Jun 97 6:32 am  
 Sample : 2600.07  
 Misc : 2537-G  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Vial: 53  
 Operator: Skelton  
 Inst : FID/TCD  
 Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	218304	10.681 mg/L m
Spiked Amount 10.000		Recovery =	106.81%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L

Quantitation Report


Data File : C:\HPCHEM\1\DATA\970602\T01524.D  
Acq On : 4 Jun 97 6:32 am  
Sample : 2600.07  
Misc : 2537-G  
IntFile : autoint1.e

Vial: 53  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01525.D  
 Acq On : 4 Jun 97 7:17 am  
 Sample : 2600.08  
 Misc : 2537-H  
 IntFile : autoint1.e

Vial: 54  
 Operator: Skelton  
 Inst : FID/TCD  
 Multiplr: 1.00

Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
-----			
System Monitoring Compounds			
1) s o-terphenyl	13.68	207969	10.175 mg/L m
Spiked Amount 10.000		Recovery =	101.75%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L


Quantitation Report

Data File : C:\HPCHEM\1\DATA\970602\T01525.D  
Acq On : 4 Jun 97 7:17 am  
Sample : 2600.08  
Misc : 2537-H  
IntFile : autoint1.e  
Quant Time: Jun 4 9:25 1997 Quant Results File: TPH7.RES

Vial: 54  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



28



Quantitation Report


Data File : C:\HPCHEM\1\DATA\970602\T01526.D  
Acq On : 4 Jun 97 8:08 am  
Sample : 2600.09  
Misc : 2537-I  
IntFile : autoint1.e

Vial: 55  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Time: Jun 4 9:26 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01526.D Vial: 55  
 Acq On : 4 Jun 97 8:08 am Operator: Skelton  
 Sample : 2600.09 Inst : FID/TCD  
 Misc : 2537-I Multiplr: 1.00  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:26 1997 Quant Results File: TPH7.RES

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
System Monitoring Compounds			
1) s o-terphenyl	13.68	241513	11.817 mg/L m
Spiked Amount 10.000	Recovery	=	118.17%
Target Compounds			
2) t tphc	0.00	0	N.D. mg/L

Quantitation Report (OT Reviewed)

Data File : C:\HPCHEM\1\DATA\970602\T01527.D  
 Acq On : 4 Jun 97 8:54 am  
 Sample : 2600.10  
 Misc : 2537-DUP  
 IntFile : autoint1.e  
 Quant Time: Jun 4 9:26 1997 Quant Results File: TPH7.RES

Vial: 56  
 Operator: Skelton  
 Inst : FID/TCD  
 Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
 Title : TPHC Calibration 01/17/97  
 Last Update : Tue Jun 03 09:01:30 1997  
 Response via : Initial Calibration  
 DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
 Signal Phase : HP-5  
 Signal Info : 30m x 0.32mm

Compound	R.T.	Response	Conc Units
<b>System Monitoring Compounds</b>			
1) s o-terphenyl	13.68	218079	10.670 mg/L m
Spiked Amount 10.000		Recovery =	106.70%
<b>Target Compounds</b>			
2) t tphc	0.00	0	N.D. mg/L


Quantitation Report

Data File : C:\HPCHEM\1\DATA\970602\T01527.D  
Acq On : 4 Jun 97 8:54 am  
Sample : 2600.10  
Misc : 2537-DUP  
IntFile : autoint1.e  
Quant Time: Jun 4 9:26 1997 Quant Results File: TPH7.RES

Vial: 56  
Operator: Skelton  
Inst : FID/TCD  
Multiplr: 1.00

Quant Method : C:\HPCHEM\1\METHODS\TPH7.M (Chemstation Integrator)  
Title : TPHC Calibration 01/17/97  
Last Update : Tue Jun 03 09:01:30 1997  
Response via : Multiple Level Calibration  
DataAcq Meth : TPH7.M

Volume Inj. : 1 ul  
Signal Phase : HP-5  
Signal Info : 30m x 0.32mm



## LABORATORY DELIVERABLES CHECKLIST AND NON-CONFORMANCE SUMMARY

THIS FORM MUST BE COMPLETED BY THE LABORATORY OR ENVIRONMENTAL CONSULTANT  
AND ACCOMPANY ALL DATA SUBMISSIONS

The following Laboratory Deliverables checklist and Non-Conformance Summary shall be included in the data submission. All deviations from the accepted methodology and procedures, of performance values outside acceptable ranges shall be summarized in the Non-Conformance Summary. The Technical Requirements for Site Remediation, effective June 7, 1993, provides further details. The document shall be bound and paginated, contain a table of contents, and all pages shall be legible. Incomplete packages will be returned or held without review until the data package is completed.

**It is recommended that the analytical results summary sheets listing all targeted and non-targeted compounds with the method detection limits, practical quantitation limits, and the laboratory and/or sample numbers be included in one section of the data package and in the main body of the report.**

- |  |                                     |
|--|-------------------------------------|
| 1. Cover page, Title Page listing Lab Certification #, facility name and address, & date of report submitted | <input checked="" type="checkbox"/> |
| 2. Table of Contents submitted   | <input checked="" type="checkbox"/> |
| 3. Summary Sheets listing analytical results for all targeted and non-targeted compounds submitted           | <input checked="" type="checkbox"/> |
| 4. Document paginated and legible  | <input checked="" type="checkbox"/> |
| 5. Chain of Custody submitted  | <input checked="" type="checkbox"/> |
| 6. Samples submitted to lab within 48 hours of sample collection   | <input checked="" type="checkbox"/> |
| 7. Methodology Summary submitted   | <input checked="" type="checkbox"/> |
| 8. Laboratory Chronicle and Holding Time Check submitted   | <input checked="" type="checkbox"/> |
| 9. Results submitted on a dry weight basis   | <input checked="" type="checkbox"/> |
| 10. Method Detection Limits submitted  | <input checked="" type="checkbox"/> |
| 11. Lab certified by NJDEP for parameters of appropriate category of parameters or a member of the USEPA CLP | <input checked="" type="checkbox"/> |

Laboratory Manager or Environmental Consultant's Signature  
Date 11/16/97



Laboratory Certification #13461

\*Refer to NJAC 7:26E - Appendix A, Section IV - Reduced Data Deliverables - Non-USEPA/CLP  
Methods for further guidance

**APPENDIX F**  
**GROUNDWATER ANALYTICAL DATA PACKAGE**

**US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY**  
**NJDEPE # 13461**

**REPORT OF ANALYSIS**

**Client:** U.S. Army  
DPW, SELFM-PW-EV  
Bldg. 173  
Ft. Monmouth, NJ 07703

**Project:** Volatiles - EPA Method 624  
96-1262  
B.2537

**Project #** 2641  
**Date Rec.** 06/05/97  
**Date Compl.** 06/06/97  
**Released by:**

**Daniel K. Wright**  
**Laboratory Director**

## Methodology Summary

### EPA Method 624 - Aqueous

This is a purge and trap gas chromatograph/mass spectrometer (GC/MS) method. The organic compounds are separated by the gas chromatograph and detected using the mass spectrometer.

An HP6890/6890 GC/MS was used with a capillary column (RTX-502.2 0.25mm ID).

Method detection limits are as stated.



**US ARMY FT. MONMOUTH ENVIRONMENTAL LABORATORY**  
**NJDEPE # 13461**

**Definition of Qualifiers**

**MDL** : Method Detection Limit

**J** : Compound identified below detection limit

**B** : Compound in both sample and blank

**D** : Results from dilution of sample

**U** : Compound searched for but not detected



# Fort Monmouth Environmental Testing Laboratory

Bldg. 173, SELFM-PW-EV, Fort Monmouth, NJ 07703

Tel (908)532-4359 Fax (908)532-3484 EMail:appleby@doim6.monmouth.army.mil

NJDEP Certification #13461

## Chain of Custody Record

Customer: <u>GENE LESINSKI-DPW</u>		Project No: <u>96-1262</u>		Analysis Parameters						Comments:		
Phone #: <u>20989</u>		Location: <u>B.2537</u>		TPHC	VOCs/15							
( ) DERA (X) OMA ( ) Other: _____		Samplers Name / Company: <u>GARY DIMARTINIS-TVS</u>				Sample #						
Lab Sample I.D.	Sample Location	Date	Time	Type	bottles						Remarks / Preservation Method	
<u>2461.01</u>	<u>2537-SW</u>	<u>6-5-97</u>	<u>1147</u>	<u>AQ</u>	<u>3</u>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>					<u>STANDING WATER</u> * <u>IN EXCAVATION</u>
												* = SAMPLES KEPT BELOW 4°C.
												VOA's preserved w/ HCl
Relinquished by (signature): <u>[Signature]</u>		Date/Time: <u>6-5-97 11415</u>		Received by (signature): <u>[Signature]</u>		Date/Time:		Received by (signature):				
Relinquished by (signature):		Date/Time:		Received by (signature):		Date/Time:		Received by (signature):				
Report Type: ( ) Full, (X) Reduced, ( ) Standard, ( ) Screen / non-certified.						Remarks:						
Turnaround time: ( ) Standard 4 wks, ( ) Rush _____ Days, (X) ASAP Verbal _____ Hrs.												

**Volatile Analysis Report**  
**U.S. Army, Fort Monmouth Environmental Laboratory**  
**NJDEP Certification #13461**

Data File Name **V00905.D**  
 Operator **Skelton**  
 Date Acquired **06/ 7/97 12:49**

Sample Name **2641.01**  
 Field ID **2537-SW**  
 Sample Multiplier **1**

CAS#	Name	R.T.	Response	Amount	MDL	GW Criteria
107028	Acrolein			not detected	6.25 ug/L	na
107131	Acrylonitrile			not detected	6.25 ug/L	na
75650	tert-Butyl alcohol			not detected	12.50 ug/L	na
1634044	Methyl-tert-Butyl ether			not detected	1.25 ug/L	na
108203	Di-isopropyl ether			not detected	1.25 ug/L	na
	Dichlorodifluoromethane			not detected	3.63 ug/L	na
74-87-3	Chloromethane			not detected	0.79 ug/L	30
75-01-4	Vinyl Chloride			not detected	2.61 ug/L	5
74-83-9	Bromomethane			not detected	1.45 ug/L	10
75-00-3	Chloroethane			not detected	2.20 ug/L	na
75-69-4	Trichlorofluoromethane			not detected	1.31 ug/L	na
75-35-4	1,1-Dichloroethene			not detected	0.74 ug/L	2
67-64-1	Acetone			not detected	1.57 ug/L	700
75-15-0	Carbon Disulfide			not detected	0.54 ug/L	na
75-09-2	Methylene Chloride			not detected	1.66 ug/L	2
156-60-5	trans-1,2-Dichloroethene			not detected	0.50 ug/L	100
75-35-3	1,1-Dichloroethane			not detected	0.83 ug/L	70
108-05-4	Vinyl Acetate			not detected	2.07 ug/L	na
78-93-3	2-Butanone			not detected	2.06 ug/L	300
	cis-1,2-Dichloroethene			not detected	0.65 ug/L	10
67-66-3	Chloroform			not detected	0.43 ug/L	6
75-55-6	1,1,1-Trichloroethane			not detected	0.81 ug/L	30
56-23-5	Carbon Tetrachloride			not detected	1.20 ug/L	2
71-43-2	Benzene			not detected	0.51 ug/L	1
107-06-2	1,2-Dichloroethane			not detected	1.27 ug/L	2
79-01-6	Trichloroethene			not detected	0.94 ug/L	1
78-87-5	1,2-Dichloropropane			not detected	0.78 ug/L	1
75-27-4	Bromodichloromethane			not detected	0.77 ug/L	1
110-75-8	2-Chloroethyl vinyl ether			not detected	1.05 ug/L	na
10061-01-5	cis-1,3-Dichloropropene			not detected	0.60 ug/L	na
108-10-1	4-Methyl-2-Pentanone			not detected	1.33 ug/L	400
108-88-3	Toluene			not detected	0.73 ug/L	1000
10061-02-6	trans-1,3-Dichloropropene			not detected	1.43 ug/L	na
79-00-5	1,1,2-Trichloroethane			not detected	1.49 ug/L	3
127-18-4	Tetrachloroethene			not detected	0.92 ug/L	1
591-78-6	2-Hexanone			not detected	1.12 ug/L	na
126-48-1	Dibromochloromethane			not detected	1.36 ug/L	10
108-90-7	Chlorobenzene			not detected	0.66 ug/L	4
100-41-4	Ethylbenzene			not detected	1.14 ug/L	700
1330-20-7	m+p-Xylenes			not detected	2.53 ug/L	na
1330-20-7	o-Xylene			not detected	1.92 ug/L	na
100-42-5	Styrene			not detected	1.57 ug/L	100
75-25-2	Bromoform			not detected	1.68 ug/L	4
79-34-5	1,1,2,2-Tetrachloroethane			not detected	1.71 ug/L	2
541-73-1	1,3-Dichlorobenzene			not detected	2.51 ug/L	600
106-46-7	1,4-Dichlorobenzene			not detected	3.08 ug/L	74
95-50-1	1,2-Dichlorobenzene			not detected	2.75 ug/L	600

1E  
VOLATILE ORGANICS ANALYSIS DATA SHEET  
TENTATIVELY IDENTIFIED COMPOUNDS

FIELD ID.

**2537-SW**


Lab Name: FMETL Project: 961262  
Cert. No. 13461 Case No.: 2641 Location: B2537 SDG No.: \_\_\_\_\_  
Matrix: (soil/water) WATER Lab Sample ID: 2641.01  
Sample wt/vol: 5.0 (g/ml) ML Lab File ID: V00905.D  
Level: (low/med) LOW Date Received: 06/05/97  
% Moisture: not dec. \_\_\_\_\_ Date Analyzed: 06/07/97  
GC Column: RTX-502 ID: 0.25 (mm) Dilution Factor: 1.0  
Soil Extract Volume: \_\_\_\_\_ (uL) Soil Aliquot Volume: \_\_\_\_\_ (uL)

CONCENTRATION UNITS:

Number TICs found: 0 (ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	RT	EST. CONC.	Q
---------	----------	----	------------	---

**APPENDIX G**  
**PHOTOGRAPHS**



APRIL 1998

## PHOTOGRAPHIC LOG

UST No. 81515-27

Building 2537  
Charles Wood Area  
Fort Monmouth



**SMC Environmental Services Group**  
Engineers, Managers, Scientists, & Planners  
Valley Forge, Pennsylvania